

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- EMPIRE DRILLING CO.
 Farm- Knoll "A" No. 5

SEC. 10 T. 10 R. 25W
 NW SE SE

Total Depth. 4230'

Comm. 11-29-58

Comp. 12-12-58


Shot or Treated.

Contractor. Empire Drilg. Co.

Issued. 2-14-59

County Graham

KANSAS



Elevation. 2512' KB

CASING:

8 5/8" 152' cem w/100 sx.

5 1/2" 4023' cem w/75 sx.

D.V. Tool set @ 2174' w/100 Barrels of K

Production. 260 BOPD

Figures indicate Bottom of Formations.

surface	166
shale and shell	1400
shale and sand	1940
shale and shell	2136
Anhydrite	2180
shale and shell	2460
shale and lime	2625
shale, shell & lime	2800
shale and lime	3085
lime and shale	3335
shale and lime	3405
lime and shale	3510
shale and lime	3630
lime and shale	3765
lime	4030
shale	4080
shale and lime	4145
shale	4175
shale and lime	4225
lime	4230 RTD
Total Depth	

TOPS:

Anhydrite (scout)	2136
Heebner	3750
Toronto	3772
Lansing-Kansas City	3787
Base Kansas City	4014
Cherokee Group	4211