


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- Knoll No. 1

SEC. 13 T. 10 R. 25W
SE SE NW

Total Depth. 3963'
Comm. 10-28-57 Comp. 11-8-57
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 1-4-58

County Graham
KANSAS



CASING:

8 5/8" 214' cem. w/175 sx

Elevation. 2433' KB

Production. Dry

Figures Indicate Bottom of Formations.

sand, shale & shells	214
shale & shells	1310
shale, shells & iron	1660
shale, shells & sand	2075
anhydrite	2132
shale & shells	2700
shale & lime	3720
lime	3963 RTD
Total Depth	

TOPS:

Anhydrite	2075
Heebner	3694
Toronto	3716
Lansing	3731
Base/Kansas City	3960

D.S.T. #1. 3723-42 Open 1 hr. Rec.
10' mud with oil specks. BHP 650#.
D.S.T. #2. 3768-85 Open 1 hr. Rec.
10' mud. BHP 0#.
D.S.T. #3. 3799-3807 Open 1 hr.
Rec. 15' thin drilling mud. BHP
1350#.
D.S.T. #4. 3808-25 Open 1 hr. Rec.
40' muddy water. BHP 1380#.
D.S.T. #5. 3876-3920 Open 1 hr. Rec.
20' mud with few specks of oil.
BHP 30#.