

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 065 — 21,322
County Number

Operator

American Energies Corporation

Address

575 Fourth Financial Center, Wichita, Ks. 67202

Well No.

1

Lease Name

Hanna

Footage Location

1650' feet from (N) 1/4 line 330' feet from (E) 1/4 line

Principal Contractor

Slawson Drilling

Geologist

Charley Shank

Spud Date

11-11-80

Date Completed

11-19-80

Total Depth

4080'

P.B.T.D.

Directional Deviation


Oil and/or Gas Purchaser

State Geological Survey
WICHITA
S. 18 T. 10S R. 25E WCH

Loc. NE SE NE

County Graham Co., Ks.

640 Acres



Locate well correctly

Elev.: Gr. 2545

DF 2548 KB 2551

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Csg.	12 1/4"	8 5/8"	23#	187'	60-40POZ	190	2% gel, 3% c.c.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbis.	MCF	bbis.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator American Energies Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole	
Well No. 1	Lease Name Hanna		
S. 18 T. 10 S. R. 25 E. W.			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
DST#1 3829-60' 30(30)30(30). Weak blow 30 min. and died. Rec. 20' watery mud with scum of oil on top of tool. IHP 1746#, FHP 1749#, IFP 41-49, FFP 57-57#, ISIP 496#, FSIP 331#. Temp. 110° DST#2 3869-3900' 30(30)30(60). Rec. 540' Water with scum of oil. SIPs 732 & 732#, FPS 57-124# & 165-206#, Temp. 114°. DST#3 3898-3960' 30(30)30(60). Weak steady blow throughout. Rec. 120' oil specked mud. IHP & FHP 1943#, IFP 49-57#, FFP 66-74#, ISIP 413, FSIP 331#. Temp. 112°. DST#4 3959-97' 30(30)30(60). Fair blow throughout. Rec. 30' G&OCM, 25% oil. 60' Gassy muddy oil, 60% oil. IHP & FHP 1956#, IFP 41-49# FFP 49-57#, ISIP 791#, FSIP 1044# DST#5 4002-52' 30(30)30(30). Very weak blow for 30 min. Rec. 15' oil specked mud. ISIP & FSIP 48# IFP 39-39#, FFP 39-39#. Temp. 112°. D&A	Anhy Heebner Lsg B/KC LTD	Electric Log 2172 + 379 3774 - 1223 3811 - 1260 4044 - 1493 4080 - 1529	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Operations Manager 12-8-80 Date		

5678L