

GEOLOGICAL SOCIETY
208 East Murc
Wichita, Kansas

AUG 15 1970

#2 Brungardt "A" #2

GARNETT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

22-10-25W
SW NE - W

Elev. 2535' KB

BRUNGARDT "A" #2

SW NE SW Section 22-10S-25W
Graham County, Kansas

P100 BOPD + 10% with
LKC (CR 42)

Commenced: June 8, 1970
Completed: June 18, 1970

OPERATOR - Derrick-American Oil Inc., 510 Petroleum Building, Wichita, Kansas

DEPTH		FORMATION	REMARKS
From	To		
0	209	Surface soil, red bed and shale	Ran 10 joints used 28 5/8" casing, set at 207' w/150 sacks GLS.
209	1800 1800?	Shale and shells	
1800	2155 2155	Shale	
2155	2193 2193	Anhydrite	
2193	2340 2340	Shale and lime	
2340	3320 2920	Lime and shale	
3320	3971 3971	Lime	
3971	4080 4080	Lime and shale	
4080	TD		



Heckner 3786
Lancaster 3807
LKC 3821

Ran 134 joints of used 5-1/2" casing set at 4079-1/2 with 125 sacks salt saturated common cement.

I, J. S. SUTTON, Certify this is a correct copy of the Drillers' Log for the well drilled in the SW NE SW Section 22-10S-25W, Graham County, Kansas, to the best of my knowledge and belief.

J. S. Sutton