

744.

Operator
C-G DRILLING CO.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWGW, ETC.:
DRY HOLE

Well No.
#6

Lease Name
KNOLL

S 24 T 10 R 25 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
SHALE	0	1685		
SAND	1685	1885		
RED BED & SHALE	1885	2120		
ANHYDRITE	2120	2162		
SHALE & SHELLS	2162	2872		
LIME & SHALE	2872			
PLUG BACK TO 1600'	1600	2145		
ANHYDRITE	2145	2162		
SHALE & SHELLS	2162	2870		
LIME & SHALE	2870	3750		
LIME	3750	4020		
DST #1 3796'-3812' 30-30-30-30 REC 45' SOSM IBHP 458# FBHP 389# IFP 22# FFP 45#				
DST #2 3900'-3920' 30-30-30-30 REC 20' MUD IBHP 137# FBHP 91# IFP 22# FFP 22#				
DST #3 3926'-3980' 30-30-30-30 WEAK 8 MIN BLOW REC 20' MUD IBHP 68# FBHP 57# IFP 45 FFP 45#				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Phyllis Buchanan
Phyllis Buchanan
Office Manager

Title

January 20, 1977

Date

8L98L