

SIDE ONE

AFFIDAVIT OF COMPLETION FORM

29-10-25W

(REV) ACO-1

This form shall be filed in duplicate with the Kansas Corporation Commission, 2000 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, SWD and injection.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.).

KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Kissinger Exploration, Inc.

API NO. 15-065-21,612

ADDRESS 410 17th Street, Suite 850,

COUNTY Graham

Denver, Colorado, 80202

FIELD Wildcat

**CONTACT PERSON Richard W. Benner

PROD. FORMATION None

PHONE (303) 623-0547

LEASE Bellerive

PURCHASER None

WELL NO. 9-29

ADDRESS

WELL LOCATION NE $\frac{1}{4}$ SE $\frac{1}{4}$

DRILLING Kissinger Drilling, Inc.

1980 Ft. from South Line and

CONTRACTOR

660' Ft. from East Line of

ADDRESS 410 17th Street, Suite 850

the SEC. 29 TWP. 10S RGE. 25W

Denver, CO 80202

WELL PLAT

PLUGGING Kissinger Drilling, Inc.

CONTRACTOR

ADDRESS 410 17th Street, Suite 850

Denver, CO 80202

KCC
KGS
(Office
Use)

TOTAL DEPTH 4092 PBTD

SPUD DATE 4/6/82 DATE COMPLETED 4/16/82

ELEV: GR 2510 DF 2521 KB 2522

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Set 362.74' 8/58"

Amount of surface pipe set and cemented at 372' w/250 sax. DV Tool Used? No

AFFIDAVIT

STATE OF COLORADO, COUNTY OF DENVER SS, I,

RICHARD W. BENNER OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS PRESIDENT (FOR)(OF) KISSINGER EXPLORATION, INC.

OPERATOR OF THE BELLERIVE LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 9-29 ON

SAID LEASE HAS BEEN COMPLETED AS OF RECEIVED DAY OF APRIL, 19 82, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

State Geological Survey
WICHITA BRANCH

SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Topeka	3589			29-10-
Heebner	3813			
Toronto	3837			
Lansing-Kansas City	3853			
Base of Kansas City		4084		
DRILL STEM TESTS				
DST #1: 3847-3894', Open 30 minutes, SI 45, OP 30, SI 45, Rec'd 2100' salt wa with scum of oil on top. PRESSURES: IF 613-1067; FF 1230-1272; ISI 1272; FSI 1272; IH 1950; FH 1929, BHT 118°				
DST #2: 4002-4017'; Open 30 minutes, SI 30, OP 30, SI 30, No blow, flushed to twice; Rec'd 5' oil spotted mud w/spots of free oil on tool PRESSURES: IF 33-44; FF 44-44; ISI 77; FSI 55, IH 2037; FH 2014				
DST #3: 4016-4040, Open 30 minutes, SI 45, OP 60, SI 45, Rec'd 125' oil spott muddy water, PRESSURES: IF 55-60; FF 77-88; ISI 1315; FSI 1282; IH 2091; FH 2069, 1st Open - fair blow, 2½" in bucket, increasing 2nd Open 3" in bucket, slowly increasing				
DST #4: 4039-4063', Open 30 minutes; SI 30, OP 30, SI 30, Rec'd 5' drilling mud - no show of oil PRESSURES: IF 55-55; FF 55-55; ISI 1121; FSI 1121 IH 2091; FH 2069 - BHT 120° Charts indicate very tight zone tested. Weak blow on 1st open; Died in 28 minutes, very weak blow on 2nd open, died in 6 minutes				

of all strings set — surface, intermediate, production, etc. **CASING RECORD** (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface casing	12¼	8-5/8"	24#	362.74	Common	250	2% gel; 3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
NONE			NONE		
TUBING RECORD					
Size	Setting depth	Pecker set at			
NONE					