

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

Compt. \_\_\_\_\_

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5146 EXPIRATION DATE 6/30/85

OPERATOR Rains & Williamson Oil Co., Inc. API NO. 15-179-20,743

ADDRESS 435 Page Court, 220 W. Douglas COUNTY Sheridan

Wichita, Kansas 67202 FIELD Fuller Wildcat

\*\* CONTACT PERSON Juanita Green PHONE 265-9686 PROD. FORMATION Lansing

PURCHASER Clear Creek, Inc. LEASE Ziegler

ADDRESS 818 Century Plaza Building WELL NO. #1

Wichita, Kansas 67202 WELL LOCATION NE NW SE

DRILLING Rains & Williamson Oil Co., Inc. 2310 Ft. from South Line and

CONTRACTOR CONTRACTOR ADDRESS 435 Page Court, 220 W. Douglas 100 Ft. from East Line of

Wichita, Kansas 67202 T1S R1E/4(Qtr.) SEC 3 TWP10S RGE 26 (W).

PLUGGING CONTRACTOR WELL PLAT (Office Use Only)

ADDRESS KCC

KGS

TOTAL DEPTH 4304' PBTD SWD/REP

SPUD DATE 5-9-84 DATE COMPLETED 6-20-84 PLG.

ELEV: GR 2565' DF KB 2570

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 263' DV Tool Used?

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO, Other

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gallons - 28% acid	4009' - 4011'

Date of first production 6-20-84	Producing method (flowing, pumping, gas lift, etc.) Pumping	Gravity
-------------------------------------	--	---------

Estimated Production -I.P.	Oil 86 bbls.	Gas MCF	Water %	Gas:oil ratio	CFPB
----------------------------	-----------------	------------	------------	---------------	------

State Geological Survey  
WICHITA BRANCH  
JUL 1 2 1985

RELEASED

Date: JUL 1 1985

FROM CONFIDENTIAL

Williamson



*Red*

*Pi* 5/21/84  
*KCC*

DRILLER'S LOG

COMPANY: Rains & Williamson Oil Co., Inc.

SEC. 3 T. 10S R. 26W

LOC. NE NW SE

WELL NAME: Ziegler #1

COUNTY: Sheridan

RIG NO. #4

TOTAL DEPTH 4304'

ELEVATION 2565 GL 2570 KB

COMMENCED: 5-9-84

COMPLETED: 5-21-84

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 263' w/165 sx. 60/40 poz., 2% gel, 3% cc.

PRODUCTION: 5 1/2" @ 4303' w/200 sx. EA2, 300 gal. flocheck.

LOG

(Figures Indicate Bottom of Formations)

JUN 11 1985  
State Geological Survey  
WICHITA BRANCH

Shale	268
Shale & Shells	3010
Shale & Lime	3260
Lime & Shale	3429
Lime	3562
Lime & Shale	3850
Lime	3870
Lime & Shale	3969
Lime	4304
ROTARY TOTAL DEPTH	4304

**RELEASED**  
Date: JUN 1 1985  
FROM CONFIDENTIAL

JUN 25 1984

**CONFIDENTIAL**  
State Geological Survey  
WICHITA BRANCH

RECEIVED  
STATE CORPORATION COMMISSION

**RELEASED**

JUN 25 1984

JUN 10 1985

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

**FROM CONFIDENTIAL**