

WELL COMPLETION OR RECOMPLETION FORM

ACQ-1 WELL HISTORY

Operator license # 5146
name Rains & Williamson Oil Co., Inc.
address 435 Page Court, 220 W. Douglas
Wichita, KS 67202
City/State/Zip

Operator Contact Person Juanita Green

Phone

Operator license #
name Rains & Williamson Oil Co., Inc.,

Wellsite Geologist
 Phone
PURCHASER

Designate Type of Completion

☒ New Well ☐ Re-Entry ☐ Workover

☐ Oil ☐ SWD ☐ Temp Abd
☐ Gas ☐ Inj ☐ Delayed Comp.
☐ Dry ☐ Other (Core, Water Supply etc.)

if OWWO: old well info as follows:

Operator STATE C
Well Name
Comp. Date Old Total Depth A

WELL HISTORY

Dr. Method: ☒ Mud Rotary ☐ Air Rotary ☐ Cable

..2-20-85.	2-27-85.....	2-27-85.....
Spud Date	Date Reached TD	Completion Date




Total Depth
PBTD

Amount of Surface Pipe Set and Cemented at 294' feet

Multiple Stage Cementing Collar Used? ☐ Yes ☐ No

If Yes, Show Depth Set feet

Alternate 2 completion, cement circulated
fr' feet depth to w/ SX cmt

Wireline Log Rec'd

API NO. 15 -179-20,799.....

County Sheridan

...150' W of SW SE NE Sec. 3....Twp. 10S...Rge. 26...X

..... **ft North from Southeast Corner of Section**

..... 14 West from Southeast Corner of Section

(Note: locate well in section plat below)

Lease Name Ziegler "A" Well# 1

Field Name

Producing Formation

Elevation: Ground 2579 KB 2588

Section Plot

APR - 5 1985

State Geological Survey
WICHITA BRANCH

RECEIVED

STATE CORPORATION COMMISSION

MAR 27 1961

CONSERVATION DIVISION
Wichita, Kansas

✓ WATER SUPPLY INFORMATION

Source of Water:

Division of Water Resources Permit #

☐ Groundwater..... Ft North From Southeast Corner and
(Well) Ft. West From Southeast Corner

Sec Twp Rge East West

☐ Surface Water..... Ft North From Southeast Corner and
(Stream, Pond etc.)..... Ft West From Southeast Corner

Sec Twp Rge ☐ East ☐ West

☐ Other (explain)
(purchased from city, R.W.D.#)

Disposition of Produced Water: ☐ Disposal
☐ Repressuring

Docket #

INSTRUCTIONS: This form shall be completed in duplicate and filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within 90 days after completion or recompletion of any well. Rules 82-3-130 and 82-3-107 apply.

Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form. See rule 82-3-107

SIDE TWO

"A" #1

Operator Name Rains & Williamson Oil Co. Lease Name Ziegler Well# SEC. 3 TWP. 10S RGE. 26W☐ East
☐ West

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken ☐ Yes ☐ No
 Samples Sent to Geological Survey ☐ Yes ☐ No
 Cores Taken ☐ Yes ☐ No

Formation Description
☒ Log ☐ Sample

Name	Top	Bottom
Anhydrite	2222 (+366)	
B/Anhydrite	2256 (+332)	
Topeka	3589 (-1001)	
Heebner	3811 (-1223)	
Toronto	3832 (-1245)	
Lansing	3850 (-1262)	
BKC	4080 (-1492)	

DST #1 - 3845-3890, 30 (30) 60 (30).
 Rec. 20' MW, 45' mud. FP's 40-50,
 50-60. IBHP 1123, FBHP 1062.

DST #2 - 3968-3998, 30 (30) 60 (30).
 Rec. 40' MW w/scum oil, 60' MW w/sl.
 trace oil. FP's 30-50, 50-71. IBHP
 233, FBHP 223.

DST #3 - 4000-4040, 30 (30) 25 (30).
 Rec. 20' sl. OCM. FP's 40-40, 40-50.
 IBHP 60, FBHP 60.

APR - 5 1985
 State Geological Survey
 WICHITA BRANCH

RECEIVED
 STATE CORPORATION COMMISSION

MAR 27 1985

CONSERVATION DIVISION
 Wichita, Kansas

CASING RECORD

☒ new☐ used

Report all strings set - conductor, surface, intermediate, production, etc.

Purpose of string	size hole drilled	size casing set (in O.D.)	weight lbs/ft.	setting depth	type of cement	# sacks used	type and percent additives
Surface	12 1/4"	8 5/8"	23#	294'	60/40 poz.	200 sx.	2% gel., 3% cc.

PERFORATION RECORD

shots per foot specify footage of each interval perforated

Acid, Fracture, Shot, Cement Squeeze Record

(amount and kind of material used)

Depth

P1

DRILLER'S LOG *x*

COMPANY: Rains & Williamson Oil Co., Inc.

SEC. 3 T. 10S R. 26W

LOC. 150' W of SW SE NE

WELL NAME: Ziegler "A" #1

COUNTY: Sheridan

RIG NO. #11

TOTAL DEPTH 4100'

ELEVATION 2579 GL 2588 KB

COMMENCED: 2-20-85

COMPLETED: 2-27-85

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 294' w/200 sx. 60/40 poz., 2% gel, 3% cc.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Sand & Shale	284
Shale	306
Shale & Sand	1744
Sand & Shale	2110
Shale	2700
Shale & Lime	3380
Lime & Shale	3621
Shale & Lime	3810
Lime & Shale	4100
ROTARY TOTAL DEPTH	4100

APR - 5 1985
State Geological Survey
WICHITA BRANCH

STATE OF Kansas)
COUNTY OF Sedgwick)

SS:

RECEIVED
STATE CORPORATION COMMISSION

MAR 27 1985

CONSERVATION DIVISION
Wichita, Kansas