

12-10-26W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- C-G DRILLING CO. & D. G. HANSEN
Farm- Flagler No. 3

SEC. 12 T. 10 R. 26W
SE NW SW

Total Depth. 4115'
Comm. 4-25-59 Comp. 5-6-59
Shot or Treated.
Contractor. C-G Drlg.
Issued. 8-8-59

County Sheridan
KANSAS



Elevation. 2605' KB

CASING:
8 5/8" 233.04'
Meas. from top of RB.

Production. Dry

Figures Indicate Bottom of Formations.

shale	200
sand-shale	765
shale-sand	1750
shale	2145
red bed	2226
Anhydrite	2265
shell - shale	2275
shale	2290
shale-shell	2320
shale	2650
shale-lime	2915
lime-shale	3025
shale-lime	3165
lime-shale	3804
lime	3856
lime-shale	3877
lime	4020
lime-shale	4075
lime	4115
Total Depth	

TOPS: SCOUT	
Anhydrite	2226
Heebner	3826
Toronto	3845
Lansing	3863

DST 3834-56', op 30 mins., 12' mud, spks oil, BHP 1080#.

DST 3855-77', op 90 mins., 75' muddy water, BHP 965#.

DST 3883-3900', op 2 hrs., 180' muddy water, BHP 1150#.

DST 3901-17', op 2 hrs., 155' muddy water, BHP 240#.

DST 3990-4075', 1 hr., 15' mud, BHP 560#.