


DREILING OIL, INC.

Victoria, Kansas 67671

13-10-260
NE NE SE



FEB 9 1973 API# 15-179-20,328

Dreiling Oil, Inc. WELL LOG

Rt. #2

Company Victoria, Kansas 67671

Farm Gano No. B-#2

Total Depth 4,075'

Comm. 10-1-72 Comp. 10-8-72

Contractor Dreiling Oil, Inc.
Rt. #2
Victoria, Kansas 67671

Sec. 13 Twp. 10 Rng. 26W

Location NE NE SE

County Sheridan

Elevation: 2562 K. B.

2559 D. F.

2557 G. R.

Casing Record

197- 8 5/8"
4,055' 4 1/2"

Cement Record

150 sacks cement
cemented w/200 gal. B.J.
Flush & 50 sks of 50/50
Poz Mis w/2% gel & 12#
Gilsnite per sk. & 175 sks. common 12% salt
Figures Indicate Bottom of Formations

Production: POT 51 BOPD ± 50%
WTR LKC 3841-44,
3852-55 GR 40

0'	45'	Sand
45'	150'	Sand Gravel
150'	236'	Blue Shale
236'	675'	Shale
675'	2175'	Shale
2175'	2215'	Anhydrite
2215'	3575'	Shale
3575'	3694'	Shale & Lime
3694'	3824'	Lime & Shale
3824'	4075'	Lime
4075'	T.D.	

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)



I, Joe Hess, Secretary Treasurer, of Dreiling Oil, Inc.
upon oath states that the above and foregoing is a true and correct
copy from the Daily Drilling Report from the Gano B-#2.

Joe Hess
JOE HESS

subscribed and sworn to before me this 10th day of October, 1972.

Cecilia Basgall
CECILIA BASGALL NOTARY PUBLIC



Commission expires: September 13, 1976.