


DREILING OIL, INC.

APR 13 1973

Victoria, Kansas 67671

KANSAS



WELL LOG

Company **Dreiling Oil, Inc.**
Rt. #2
Victoria, Kansas 67671

Farm **Gano B** No. **7**

Total Depth **4,100'**

Comm. **1-31-73** Comp. **2-7-73**

Contractor **Dreiling Oil, Inc.**
Rt. #2
Victoria, Kansas 67671

Sec. **13** Twp. **10** Rng. **26**

Location **SW NE NE**

County **Sheridan**

Elevation: **2572** **K. B.**
2569 **D. F.**
2567 **G. R.**

Casing Record
200' - 8 5/8"
4,086' - 4 1/2"

Cement Record
165 sacks
Cemented w/10 bbl. freshwater
& 200 gal. of B.J. Flush & 50
sks Poz Mix 2% gel w/12#Gilsomite
175 sks common 12% salt

Production:

Figures Indicate Bottom of Formations

0'	105'	Top Soil & Sand
105'	140'	Hard Sand
140'	160'	Blue Shale
160'	200'	Blue Shale
200'	1580'	Shale
1580'	2192'	Shale, Sand
2192'	2215'	Anhydrite
2215'	2231'	Anhydrite
2231'	2545'	Shale
2545'	2945'	Shale & Lime
2945'	3190'	Lime & Shale
3190'	3580'	Shale & Lime
3580'	3685'	Lime, Shale
3685'	4100'	Lime
4100'	T.D.	

Log Tops	Depth
Top	3574
Heeb	3788
Tor	3811
Lans	3828
Bkc	4068
Ltd	4086

UBLIC