


KANSAS GEOLOGICAL SOCIETY 1-10-29W
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY ABERCROMBIE DRILLING
FARM Heier NO. 1

SEC. 1 T. 10 R. 29W
LOC. C NW NE

TOTAL DEPTH 4236'
COMM. 3-25-68 COMP. 4-3-68
SHOT OR TREATED
CONTRACTOR Abercrombie Drlg.
ISSUED 9-1-68
7

COUNTY Sheridan



CASING
20 10
15 7 5/8" 226' cem w/ 125 sx
12 6
13 5

ELEVATION 2831' KB

PRODUCTION DRY/BKC

FIGURES INDICATE BOTTOM OF FORMATIONS

0	189	Clay & Sand Streaks
189	200	Sand & Gravel
200	895	Shale
895	1800	Shale & Sand
1800	2075	Shale w/Sand Streaks
2075	2203	Sand
2203	2240	Red Bed Shale
2240	2875	Shale
2875	3215	Shale & Lime
3215	3485	Lime & Shale
3485	3655	Shale & Lime
3655	4005	Lime & Shale
4005	4235	Lime
	4236	Rotary Total Depth

Drill 227' of 11" surface hole and set 7-5/8" casing @226' w/125 sx. cement.
Cement circulated. Plug was down 5:00 p.m., March 25, 1968.
Dry and Abandoned.

ELECTRIC LOG TOPS:

ELEVATION:

Anhydrite	2424	(+ 407)	2831 K. B.
Howard	3612	(+ 781)	2829 D. F.
Topeka	3701	(- 870)	2823 G. L.
Heebner	3920	(-1089)	
Toronto	3950	(-1119)	
Lansing	3958	(-1127)	
Base/Kansas City	4204	(-1373)	
E.L.T.D.	4236	(-1405)	

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

A. L. Abercrombie, Abercrombie Drilling, Inc., does hereby certify that the above and foregoing is a true and correct copy of the log of the #1 HEIER, C NW/4 NE/4, Section 1-10S-29W, Sheridan County, Kansas, as reflected by the files of Abercrombie Drilling, Inc. as of the 5th day of April, 1968.