

WICHITA BRANCH
KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-179-20517

API No. 15 — 179 — 20,517
County Number

Operator

Don E. Pratt

Address

P. O. Box 370 Hays, Kansas

Well No. #1

Lease Name

Beckman

Footage Location

660

feet from (N) ~~XX~~ line 660feet from (E) ~~XX~~ line

Principal Contractor

Murfin Drilling Co.,

Geologist

Green & Green

Spud Date

8-1-78

Total Depth

4611'

P.B.T.D.

Date Completed

8-13-78


Oil Purchaser

OKC

S. 31 T. 10 R. 30 ^NW

Loc. 50' SW/C NE SW

County Sheridan

640 Acres
N

Locate well correctly

Elev.: Gr. 2974

DF 2976 KB 2979

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface csg.,	12½"	8 5/8"	20#	248'	COS	210	
Prod. string		4½"	14#	4610'	COS	250	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	DP's	4202-08 4168-74

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8"	4544'	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gals.,	

INITIAL PRODUCTION

Date of first production 8-19-78		Producing method (flowing, pumping, gas lift, etc.) swab.,		
RATE OF PRODUCTION PER 24 HOURS	Oil 64 bbl. 3 hrs., bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Don E. Pratt		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: OIL	
Well No. 1-31	Lease Name Beckman		
S <u>31</u> T <u>10</u> R <u>30</u> X _W			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
See copy of Geological report attached., Great Guns log....enclosed.,			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	DON E. PRATT BY <u><i>Susie Uberty</i></u> Signature		
	SUSIE UBERT, OFFICE MGR., Title		
	9-26-78 Date		

79153

WELL LOG

15-179-20517

COMPANY Don E. Pratt

SEC. 31 T. 10S R. 30W
LOC. 50' fsw cor. NE SW

FARM BECKMAN

NO. 1


RIG. NO. 16

TOTAL DEPTH 4612'

COMM. August 1, 1978

COMP. August 12, 1978

COUNTY Sheridan
KANSAS



CONTRACTOR Murfin Drilling Company

CASING

20 10
15 8 -5/8" @ 248' w/210 sx.
12 6
13 5
4 1/2" @ 4511' w/250 sx.

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

80'	Surface soils & Sand
195'	Sand
249'	Blue Shale
2529'	Sand & Shale
2561'	Anhydrite
2855'	Sand & Shale
3120'	Shale
3740'	Shale & Lime
3915'	Lime
4095'	Lime & Shale
4120'	Shale & Lime
4165'	Lime
4300'	Shale & Lime
4320'	Lime & Shale
4445'	Lime
4516'	Shale & Lime
4520'	Lime
4595'	Shale & Lime
4612'	Lime & Shale

RTD