

CONTRACTOR'S WELL LOG

State Geological Survey

WICHITA, BRANCH

15-193-20078

OPERATOR:
CONTRACTOR:
WELL NAME:
LOCATION:

GEOLOGIST:
SPUD DATE:
COMPLETION DATE:

COPY

Tom Jordan
Abercrombie Drilling, Inc.
HUELSMANN #1
C SE NW Section 1-10S-31W
Thomas County, Kansas
Benny Singleton
June 8, 1976
June 22, 1976

0	221	Surface Sand
221	1979	Shale
1979	2553	Shale & Sand
2553	2586	Anhydrite
2586	2850	Lime & Shale
2850	3050	Shale, Sand & Lime
3050	4002	Lime & Shale
4002	4747	Lime
	4747	Rotary Total Depth

15-193-20078
JUN 22 1976

rilled 261' of 12-1/4" hole. Ran 6 jts. used 28#, 8-5/8" casing. Tallied 248.04'. Set
256.04' with 190 sx. 2% gel, 3% ca.cl. Sun Cement. Cement did circulate. Plug was down
@ 8:00 p.m. June 8, 1976.

Ran 5-1/2", 15# casing, set @ 4136' K.B. Cemented with 50 sx. 50/50 Posmix, 2% gel, 12-1/2#
gilsonite per sack; plus 100 sx. Common cement, 2% gel, 10% salt, 4# friction reducer.
Good circulation. Plug down @ 6:15 p.m. on June 22, 1976.

SAMPLE TOPS:

Anhydrite 2554'
B/Anhydrite 2586'

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Jerry A. Langrehr, Exec. Vice President of Abercrombie Drilling, Inc., does hereby state that
the above and foregoing is a true and correct copy of the log of the HUELSMANN #1, C SE NW
Section 1-10S-31W, Thomas County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
Jerry A. Langrehr, Exec. V. P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state
as of this 24th day of June, 1976.