

Computer inventoried

35-10s-32W

COPY

Drill Stem Tests

#1 Wilson  
200'N SE SE NE 35-10s-32w  
Thomas County, Kansas

15-193-20643

DST #1-Lansing E & F 4093-4119, 30-30-30-30. Recovered 70' of mud with a few oil specks. HYD 1940-1930, FP 22-26, 47-51, SIP 1147-1139, 112°F.

DST #2-Lansing H 4151-4183, 30-30-30-30. Recovered 20' of oil cut mud (20% oil). HYD 1990-1970, FP 40-42, 48-48, SIP 317-71, 112°F.

DST #3-Lansing I, J & K 4188-4270, 30-30-30-30. Recovered 40' of GIP and 20' of oil specked mud. HYD 2039-2022, FP 54-54, 60-60, SIP 69-71, 114°F.

DST #4-4271-4294, 30-30-30-30. Recovered 5' of oil specked mud. HYD 2070-2010, FP 32-32, 32-32, SIP 32-32, 114°F.

DST #5  
4295'-4337', (Pleasanton sand) 60-60-60-60  
Recovered: 20' Gas in pipe, 1' oil, 102' oil cut mud (20% oil), 124' slightly oil cut watery mud (1% oil, 10% water), 62' watery mud (30% water), 27,000ppm Hyd: 2149-2139#, FP: 50-101#; 132-144#, SIP: 1277-1256#.

DST #6 4568'-4599' Cherokee sand 25-0-0-0  
Recovered: 3' mud FP: 30-30#