

OCT 23 1981
CONFIDENTIAL

KANSAS DRILLERS LOG

State Geological Survey
WICHITA BRANCH

S. 9 T. 10 R. 32W
 Loc. C NE SW
 County Thomas

API No. 15 — 193 — 20,182
 County Number

Operator
DONALD C. SLAWSON

Address
200 Douglas Building Wichita, Kansas 67202

Well No. 1 Lease Name Saltzman 'A'

Footage Location
2000' feet from XEN (S) line 2040' feet from XEN (W) line

Principal Contractor Slawson Drilling Company, Inc. Geologist Ralph Ruwwe

Spud Date March 15, 1979 Total Depth 4760 P.B.T.D. NA

Date Completed March 25, 1979 Oil Purchaser NA

640 Acres
 N

RELEASED
 APR 30 1982
 FROM CONFIDENTIAL
 Elev.: Gr. 3077
 DF 3079 KB 3082

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	28#	314'	60/40 poz	225sx	2% gel; 3%cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB
	bbls.	MCF	bbls.		
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

79523

Operator DONALD C. SLAWSON		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Saltzman 'A'	Dry Hole
S 9 T 10 R 32 W ^E _W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
0 - 169 Shale and sand			<u>LOG TOPS</u>	
169 - 318 Surface				
318 - 565 Shale and sand				
565 - 1875 Shale and shells			ANH 2608 (+474)	
1875 - 2609 Shale and sand			B/ANH 2636 (+446)	
2609 - 2836 Anhydrite			WAB 3673 (-591)	
2836 - 2978 Shale			HEEB 4024 (-942)	
2978 - 4050 Lime and shale			TOR 4048 (-966)	
4050 - 4310 Lime			LANS 4062 (-980)	
4310 - 4394 Lime and shale			STK 4286 (-1204)	
4394 - 4420 Lime			B/KC 4348 (-1266)	
4420 - 4470 Lime and shale			MARM 4380 (-1298)	
4470 - 4620 Lime			PAW 4476 (-1394)	
4620 - 4760 Lime and shale			L/CHER 4570 (-1488)	
4760 RTD			JH ZN 4615 (-1533)	
			MISS 4660 (-1578)	
			LTD 4760 (-1678)	
DST #1 4023-50 (TOR) 30-30-45-60, VWBTO, Rec. 60' Mud, NS. IFP 9-18#, ISIP 1293#, FFP 18-36#, FSIP 1293#.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature
	R.J. THATCHER - Engineer
	Title
	April 22, 1979
	Date

CONFIDENTIAL

OPERATOR: Donald C. Slawson
200 Douglas Building
Wichita, Kansas 67202

State Geological Survey
WICHITA BRANCH

LEASE: #1 Saltzman 'A'
C NE SW of Sec. 9-10-32W
Thomas County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: March 15, 1979

COMPLETED: March 25, 1979

CASING: Surface - 8 5/8" @ 314' w/225 sx 60/40 poz

0 -	169	Shale and sand
169 -	318	Surface
318 -	565	Shale and sand
565 -	1875	Shale and shells
1875 -	2609	Shale and sand
2609 -	2836	Anhydrite
2836 -	2978	Shale
2978 -	4050	Lime and shale
4050 -	4310	Lime
4310 -	4394	Lime and shale
4394 -	4420	Lime
4420 -	4470	Lime and shale
4470 -	4620	Lime
4620 -	4760	Lime and shale
4760		RTD

STATE OF KANSAS)
)
COUNTY OF SEDGWICK) SS.

I, R.J. THATCHER, of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Saltzman 'A' test.



R.J. THATCHER

Subscribed and sworn to before me this 22nd day of April, 1979.