

State Geological Survey
KANSAS DRILLERS LOG
WICHITA, BRANCH

API No. 15 — 193 — 20,055
County Number

Operator

Donald C. Slawson

Address

408 One Twenty Building Wichita, Kansas 67202

Well No.

#2

Lease Name

Meek "A"

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Slawson Drlg. Co.

Geologist

Ralph Ruwwe

Spud Date

12-1-74

Total Depth

4655

P.B.T.D.

4617

Date Completed

12-16-74

Oil Purchaser


APCO

S. 32 T. 10 R. 32 W

Loc. 150 N NE SW

County Thomas

640 Acres
N



Elev.: Gr. 3076

DF 3078 KB 3081

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	28	293'	60/40 Poz	225 sx	
Production	7 7/8"	4 1/2"	10.5	4668	50/50 Poz	225 sx	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	1/2" jets	
			2	1/2" jets	

TUBING RECORD

Size	Setting depth	Packer set at			
2 3/8"	4581				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1000 GA MOD 202,	4568-71, 4576-82, 4568-71
1500 GA NE 28%	4229, 4256, 4290
1500 GA NE 28%	4061, 4161, 4178

INITIAL PRODUCTION

Date of first production 1/8/75	Producing method (flowing, pumping, gas lift, etc.) Pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 135 bbls. Gas no MCF Water no bbls. Gas-oil ratio N/a CFPB
Disposition of gas (vented, used on lease or sold) N/A	Producing interval (s) Cherokee & L/KC

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Donald C. Slawson		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 2	Lease Name Meek 'A'	Oil
S 32 T 10 R 32 W E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Hole	0	323	Anhydrite	2572 (+509)
Shale and Shells	323	1018	Heebner	3989 (-908)
Shale and Sand	1018	2520	Toronto	4009 (-928)
Shale	2520	2573	Lansing	4028 (-947)
Anhydrite	2573	2603	Stark	4242 (-1161)
Shale and Lime	2603	4420	B/KC	4305 (-1224)
Lime	4420	4530	Marmaton	4339 (-1258)
Lime with Shale	4530	4593	Pawnee	4440 (-1359)
Lime	4593	4655	L/Cherokee	4522 (-1441)
RTD	4655		Conglomerate	4589 (-1508)
			Miss. Lime	4627 (-1546)
DST #1 4046-4103, 30,45,45,60, strong blow throughout, rec. 230' GIP & 870' total fluid 45' Clean Oil (Gr 38 Corr.) 100' muddy oil, 160' VHOC Wtry Mud (60% Oil-30% Wtr) 565' Salt Wtr. ISIP 1289, FSIP 268-411.				
DST #2 4107-4116, 30,45,45,60, V weak, blow throughout, rec. 40' mud, no show. ISIP 1298, FSIP 1298#.				
DST #3 4150-4200, 30,45,45,60, strong blow throughout, rec. 840' GIP & 420' total fluid, 55' VHOCM, 365' gassy oil (Gr 39 Corr) ISIP 1307-1289#.				
DST #4 4184-4213, 30,45,45,60, good blow throughout, rec. 270' GIP, 150' total fluid, 60' OC gassy mud (10% oil), 90' VHOC gassy mud 950% oil) no wtr. ISIP 1307, FSIP 1307#.				
DST #5 4214-4250, 30,45,45,60, strong blow throughout, GTS-50' rec. 2160' total fluid, 1950' clean gassy oil, 210' muddy oil, no wtr, ISIP 1235#-1226#.				
DST #6 4242-4270, 30,45,45,60, strong blow throughout, GTS, 40* rec. 270' total fluid 90' HOCM, 110' muddy gassy oil, 80' sli mdy gassy oil, ISIP 662 FSIP 608#.				
DST #7 4275-4315, 30,45,45,60, strong blow throughout, rec. 420' total fluid, 45' OCM 375' gsy, ski, mdy, oil ISIP 1073-1037.				
DST #8 4346-4530, 30,45,60, 45, weak blow 57" and died. Rec. 50' mud, no show ISIP 500#-FSIP 196#.				

USE ADDITIONAL

Date Received 10/15/55	RECEIVED OCT 15 1955 SAND OIL FIELD SAND OIL FIELD SAND OIL FIELD
---------------------------	---

1000 GA MOD 202: Trtd at rt of 3 BPM, 500-550#, ISIP 400#, on vac/2": 112 BLW, Set 2 hrs: Started Swbg rec. 40 BLW, well went on oil: Swbd 16.32 BOPH (OB), no wtr: 1250' FU/ON (all oil): Set RBP 4350: Perf 4290-4256; 4229 1 8/ft: Swb tstd 1.34 BOPH (nat), No wtr: Limited entry trtd 1500 GA NE 28%, rate 6 BPM, 15-1600#, ISIP 200#, vac/2": 11 BLW, Swbd back 60 BLW, went on oil: Tested 40 BOPH (1000' OB): SION.

3400' FU (NW): Perf 1 8 4161: Swbd 1.16 BOPH, (NW): Perf 1 8 4061: Swb tstd 1.16 BOPH (NW): Perf 1 8 4178: Swbd 1.16 BOPH, (NW): Limited entry trtd w/1500 GA NE 28%, TP 1350#, 6.5 BPM, 111 BLW: Swbd approx 60 BLW: Swb tstd 32 BOPH (Tr wtr), 1100' OB: SION. Prep to pull RBP: Perf today as follows: 4289-91, 4254-56, 4228-30, 4177-79, 4160-62, 40 60-62. Will equip w/tbg & rds & final w/ST.

7096L

WICHITA

Feb 27

WELL LOG

32-10-32W

15-193-20,055

COMPANY: Donald C. Slawson
408 120 Building
Wichita, Kansas 67202

LEASE: Meek 'A' #2 32-10-32W
150' N NE SW
Thomas County, Kansas

TOTAL DEPTH: 4655 feet

CONTRACTOR: Slawson Drilling Company, Inc.

COMPLETED: November 30, 1974

COMPLETED: December 16, 1974

CAVING: Set 8 5/8" @ 293' w/225 ex

0-323	Surface hole
323-1018	Shale and Shells
1018-2520	Shale and Sand
2520-2573	Shale
2573-2603	Anhydrite
2603-4420	Shale and Lime
4420-4530	Lime
4530-4593	Lime with shale
4593-4655	Lime
4655	RTD



STATE OF KANSAS }
COUNTY OF SEDGWICK } SS.

I, JAMES C. REMSBERG, of the Slawson Drilling Company, Inc,
do hereby state that the above and foregoing is a true and correct copy of the
log of the Meek 'A' #2 well.

James C. Remsberg
JAMES C. REMSBERG

Subscribed and sworn to before me this 31st day of
December, 1974.

Dolores B. Coady
Dolores B. Coady, Notary Public

My Commission Expires:

Notary Public Seal