


KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCHAPI No. 15 — 193 — 20079
County NumberS. 9 T. 10 R. 33W ^E_W
Loc. 150' SW of SW SWCounty Thomas640 Acres
N

Locate well correctly

Elev.: Gr. 3178DF 3180 KB 3183

Operator

Donald C. Slawson & Petroleum, Inc.

Address

408 120 Bldg. Wichita, Ks. 67202

Well No.

1

Lease Name

Nollette 'M'

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Slawson Drlg. Co., Inc.

Geologist

George Mueller

Spud Date

May 15, 1976

Total Depth

4822

P.B.T.D.

Date Completed

May 26, 1976

Oil Purchaser

N/A

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$ "	8 5/8"		363'	60/40 Poz	250 sx	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Donald C. Slawson & Petroleum, Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1	Lease Name Nollette 'M'		Dry Hole
S <u>9</u> T <u>10</u> R <u>33W</u> W		MAR 17 1977	
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Surface Hole	0	365	
Sand & Shale	365	2606	
Shale	2606	2695	
Anhydrite	2695	2719	
Lime & Shale	2719	3845	
Lime	3845	4822	
RTD	4822		
DST #1 4284-4320 (160' zn), VWB inc to FB, 30-45-45-60, Rec. 130' TF, 5' MO, 125' HOCM, (50% M, 40% O, 10% G) NW, IFP 35-70#, ISIP 1264#, FFP 70-88#, FSIP 1211# DST #2 4319-4347 Packer Failed DST #3 4317-4347 Packer Failed DST #4 4314-4347, (180' zn) WB died 4", 30-45-30-60, Rec. 10' Mw/spts O, IFP 26-35#, DST #5 4340-4372, (ST. SH) WB, Rec. 30 SLOCM, IFP 26-35#, ISIP 1089#, FFP 35-53#, FSIP 440# Drlg @ 4630' DST #6 4608-4695, 30-45-45-60, (JH ZN), W-VWB, Rec. 20' M, NS, IFP 55-78#, ISIP 173#, FFP 78-78#, FSIP 95#		LOG TOPS ANH 2693 (+490) B/ANH 2722 (+461) HEEB 4082 (-899) LANS 4123 (-940) ST SH 4341 (-1158) B/KC 4400 (-1217) MARM 4422 (-1239) L/CK 4615 (-1432) B/SD 4710 (-1527) MISS 4721 (-1538) LTD 4822 (-1639)	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Rene M. Stucky, Engineering Assistant Title June 15, 1976 Date		

GL06L

State Geological Survey
WICHITA, BRANCH

WELL LOG

15-193-20079

9-10-33W

OPERATOR: Donald C. Slawson & Petroleum, Inc.
408 120 Bldg.
Wichita, Kansas 67202

LEASE: #1 Nollette 'M'
150' SW of SW SW Sec. 9-10-33W
Thomas County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.

COMMENCED: May 15, 1976

COMPLETED: May 26, 1976


CASING: Set 8 5/8" @ 363' w/250 sx

TOTAL DEPTH: 4822'

0 - 365	Surface Hole
365 - 2606	Sand & Shale
2606 - 2695	Shale
2695 - 2719	Anhydrite
2719 - 3845	Lime & Shale
3745 - 4822	Lime
4822	RTD

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

I, RENE M. STUCKY, of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Nollette 'M' well.


RENE M. STUCKY

Subscribed and sworn to before me this 15th day of June, 1976