

WICHITA BRANCH  
WICHITA BRANCH

KANSAS DRILLERS LOG

K. S. LIBRARY

15-193-20158

API No. 15 — County — Number —

Operator  
Donald C. Slawson

Address  
200 Douglas Building, Wichita, Kansas 67202

Well No. #1 Lease Name Krug

Footage Location  
660' feet from (S) line 330' feet from (W) line

Principal Contractor Slawson Drilling Co., Inc. Geologist Ralph Ruwwe

Spud Date 1/14/78 Total Depth 4800' P.B.T.D. N/A


Date Completed 1/24/78 Oil Purchaser N/A

S. 14 T. 10 R. 33W E W

Loc. W/2 SW SW

County Thomas

640 Acres  
N



Locate well correctly

Elev.: Gr. 3142

DF 3144 KB 3147

### CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	28#	343'	60/40 poz	275	2% gel, 3% cc

### LINER RECORD

### PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

### TUBING RECORD

Size	Setting depth	Packer set at


### ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

### INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
		bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Donald C. Slawson		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: dry hole	
Well No. #1	Lease Name Krug 'K'		
S 14 T 10 R 33W E W			
<b>WELL LOG</b>		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
0 - 347 Surface hole 347 - 1617 Shale and shells 1617 - 1842 Shale, shells and sand 1842 - 2213 Shale 2213 - 2514 Shale and shells 2514 - 2906 Shale 2906 - 4093 Shale and lime 4093 - 4324 Lime 4324 - 4355 Lime and shale 4355 - 4514 Lime 4514 - 4590 Lime and shale 4590 - 4746 Lime 4746 - 4800 Lime and shale 4800 RTD			LOG TOPS ANH 2649 (+498) B/ANH 2677 (+470) HEEB 4044 (-897) TORO 4064 (-917) LANS 4081 (-934) STK 4300 (-1153) B/KC 4354 (-1207) MARM 4382 (-1235) JH ZN 4636 (-1489) SD 4678 (-1531) MISS 4714 (-1567) LTD 4800 (-1653)
DST #1 4155-4167 (70' zn), VWB/20", Rec. 1' O 24°, 30' M w/spts oil, IFP 16-25# ISIP 1056#, FFP 25-25#, FSIP 738#, 110°  DST #2 4267-4302 (180' zn) 30-45-45-60, SBTO, Rec. 650' GIP, 250' CGO 40°, 55' VHOCM (45% O), IFP 33-82#, ISIP 1340# FFP 82-148#, FSIP 1310# DST #3 4267-4316 (SP) (180' zn), 30-60-45-75, SBTO, Rec. 315' GIP, 135' CGO 40°, 190' MO (75% O, NW), IFP 17-66#, ISIP 1310# FFP 74-115#, FSIP 1259# DST #4 4581-4654 (JH ZN) 30-30-30-30, WB/12" Rec. 10' VSOCM, IFP 8-8#, ISIP 131# FFP 8-8#, FSIP 33#, 120°			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	<div style="text-align: right;">             Signature            R.J. Thatcher            Title            February 18, 1978            Date         </div>		

10786L

State Geological Survey  
WICHITA BRANCH

15-193-20158

14-1033W

WELL LOG

OPERATOR: Donald C. Slawson  
200 Douglas Building  
Wichita, Kansas 67202

LEASE: #1 Krug 'K'  
W/2 SW SW Sec. 14-10-33W  
Thomas County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.  
200 Douglas Building  
Wichita, Kansas 67202

COMMENCED: January 14, 1978

COMPLETED: January 24, 1978

CASING: Surface - 8 5/8" @ 343' w/275 sx 60/40 poz

0 - 347	Surface hole
347 - 1617	Shale and shells
1617 - 1842	Shale, shells and sand
1842 - 2213	Shale
2213 - 2514	Shale and shells
2514 - 2906	Shale
2906 - 4093	Shale and lime
4093 - 4324	Lime
4324 - 4355	Lime and shale
4355 - 4514	Lime
4514 - 4590	Lime and shale
4590 - 4746	Lime
4746 - 4800	Lime and shale
4800	RTD

STATE OF KANSAS            )  
                                  )       SS.  
COUNTY OF SEDGWICK        )

I, R.J. Thatcher, of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Paris 'A'