

**KANSAS DRILLERS LOG**

State Geological Survey  
WICHITA, BRANCH

API No. 15 — 193 — 20091  
County Number

S. 15 T. 10 R. 33W E  
Loc. 400' SW of C NE SW  
County Thomas

Operator  
Donald C. Slawson & Petroleum, Inc.

Address  
408 120 Building, Wichita, Kansas 67202


Well No. #2 Lease Name Nollette '0'

Footage Location  
670 feet from (N) (S) line 1990 feet from (E) (W) line

Principal Contractor Slawson Drilling Co., Inc. Geologist Ralph Ruwwe

Spud Date September 7, 1976 Total Depth 4790' P.B.T.D.

Date Completed September 16, 1976 Oil Purchaser N/A



Elev.: Gr. 3158  
DF 3160 KB 3163

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	28	370'	60/40 pzo	225	2% gel 3% cc

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated

**INITIAL PRODUCTION**

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Donald C. Slawson & Petroleum, Inc. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: dry hole

Well No. #2 Lease Name Nollette '0'

S 15 T 10 R 33W E W


**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
0 - 373 Surface hole				
373 - 530 Shale and Shells				
530 - 1977 Shale				
1977 - 2669 Shale and Shells				
2669 - 2698 Anhydrite				
2698 - 4193 Shale and Lime				
4193 - 4348 Lime				
4348 - 4414 Lime and Shale				
4414 - 4532 Lime				
4532 - 4790 Lime and Shale				
4790 RTD				
<p>DST #1 4266-4302 (160' zn), 30-30-30-30, VWB died/10", Rec. 10' Mud, IFP 31-31#, ISIP 36#, FFP 31-31#, FSIP 31#</p> <p>DST #2 4294-4323 (180' zn), 30-30-30-30, VWB/18" &amp; died, Rec. 30' SOCM, IFP 31-36# ISIP 146#, FFP 36-41#, FSIP 62#</p> <p>DST #3 4317-4348 (200' zn), 30-45-45-60, WBTO, Rec. 135' TF, 10' SOCM, 60' SOCMW (80% W), 65' wtr, IFP 41-62#, ISIP 1281#, FFP 62-83#, FSIP 1250#</p>			<p><b>LOG TOPS</b>            ANH 2668 (+495)            B/ANH 2697 (+466)            WAB 3718 (-555)            HEEB 4057 (-894)            TORO 4077 (-914)            LANS 4101 (-988)            STK 4318 (-1155)            B/KC 4372 (-1209)            MARM 4406 (-1243)            PAWN 4518 (-1355)            U/CK 4567 (-1404)            L/CK 4601 (-1438)            JH ZN 4646 (-1483)            SD 4704 (-1541)            MISS 4709 (-1546)            LTD 4789 (-1626)</p>	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature
	Rene' M. Stucky Title
	September 30, 1976 Date

6986L

State Geological Survey

WICHITA, BRANCH

WELL LOG

15-10-33W

MAR 07 1977

OPERATOR: Donald C. Slawson & Petroleum, Inc.  
408 120 Building  
Wichita, Kansas 67202

LEASE: #2 Nollette 'O'  
Approx NE NW Sec. 15-10-33W  
Thomas County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.

COMMENCED: September 7, 1976

COMPLETED: September 16, 1976

0 - 373	Surface hole
373 - 530	Shale and Shells
530 - 1977	Shale
1977 - 2669	Shale and Shells
2669 - 2698	Anhydrite
2698 - 4193	Shale and Lime
4193 - 4348	Lime
4348 - 4414	Lime and Shale
4414 - 4532	Lime
4532 - 4790	Lime and Shale
4790	RTD

STATE OF KANSAS        )  
                              )        SS.  
COUNTY OF SEDGWICK    )

I, Rene' M. Stucky of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the #2 Nollette 'O' well.