

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-105-00003

Company- OIL CAPITOL CORP.
Farm- Shilling No. 1

SEC. 1 T. 10 R. 6W
SW SW NE

Total Depth. 4053'
Comm. 6-27-56 Comp. 7-14-56
Shot or Treated.
Contractor. Shields Drlg. Co.
Issued. 6-29-57

County Lincoln
KANSAS



CASING:
8 5/8" 315' w/125 sx cem.

Elevation. 1533' BB

Production. Dry

Figures indicate Bottom of Formations

NO DRILLER LOG AVAILABLE.

TOPS:	HALLB.
Heebner shale	2410
Douglas sandstone	2463
Lansing-Kansas City Group	2569
Basal Pennsylvanian Conglomerate	3198
Mississippian limestone	3215
Gilmore City limestone	3416
Boice shale	3478
Chattanooga shale ?	3504
Hunton limestone	3554
Maquoketa shale	3665
Viola limestone	3735
Simpson dolomite	3914
Simpson shale	3950
Simpson sand (St. Peter)	3968
Arbuckle dolomite	4011

Trace of heavy brown oil 3930-41

DST #1: 3222-3234. Open 30 min. w/strong blow throughout test; closed 20 mins. for BHP. Rec. 355' muddy salt wtr. BHP 1140#; IFP 0#; FFP 180#.

Ra n Halliburton.