

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-105-00000

Company- BRUNSON-SPINES, INC.  
Farm- Pruitt No. 1

SEC. 8 T. 10 R. 7W  
SW NE SW

Total Depth. 3695'  
Comm. 3-10-59 Comp. 3-22-59  
Shot or Treated.  
Contractor. Brunson-Spines, Inc.  
Issued. 5-30-59

County Lincoln  
KANSAS



Elevation. 1444' KB

CASING:  
3 5/8" @ 241'

Production. Dry

Figures Indicate Bottom of Formations.

lime & shale	40
lime	72
lime & shale	125
sand & gravel	170
lime & shale	220
lime, sand rock & red bed	241
lime w/strks. pyrite	435
blue shale & shells	485
red bed	590
red bed & shale	672
shale & shells	809
Anhydrite	884
lime & shale	1020
lime	1129
shale & lime	1205
lime	1304
lime & shale	1480
lime	1615
shale & strks. lime	1888
lime	1900
shy. shale	1938
lime	1950
shale & shells	2185
lime	2465
sand	2486
shale	2517
lime	2530
shale & lime	2566
lime	2925
lime & shale	3276
chert	3288
lime & chert	3359
lime	3450
shale	3470
chert	3483
lime, chert & shale	3559
lime & shale	3582
shale	3652
lime	3695
Total Depth	

TOPS:

Anhydrite (Scout)	803
Fort Riley	1082
Base Florence Flint	1204
Topeka	2187
Douglas Sand	2464
Lansing	2552
Burgess Sand	3164
Miss. Limestone	3177
Gilmore City Limestone	3358
Kinderhook Shale	3433
Hunton	3470
Maquoketa Shale	3555
Viola Limestone	3614