


15-11-1W

Company - PHILLIPS PETRO.CO.
 Farm - Kather No. 1.

SEC. 15 T. 11 R. 1W
 SWc SW

Total Depth. 3630'
 Comm. 8-1-44 Comp. 8-30-44
 Shot or Treated.
 Contractor.
 Issued. 10-21-44

County. Ottawa
 KANSAS



CASING:
 8 5/8" 279'

Elevation. 1340'

Production. Dry

Figures Indicate Bottom of Formations.

shale	83
sand	93
shale	270
lime	325
lime, sand & shale	525
lime & sand	665
shale & red bed	740
shale	900
lime & shale	1105
lime, shale & shells	1280
lime & shale	1750
lime	1830
lime & shale	1895
lime	1940
lime & shale	2045
lime	2158 1/2
lime & shale	2213 1/2
lime	2403 1/2
lime & shale	2568 1/2
shale	2608 1/2
lime & shale	2663 1/2
shale	2683 1/2
shale, lime & sand	2703 1/2
chert & lime	2827 1/2
lime	2848 1/2
lime & chert	2867
lime	2906 1/2
shale	3084 1/2
lime	3288 1/2
shale	3388 1/2
lime	3393 1/2
lime & chert	3463 1/2
lime	3538 1/2
lime & sand	3573 1/2
lime, sand & shale	3598 1/2
lime	3630
Total Depth	

Tops:

Lansing KC	2055	No Shows
Miss Dolomite	2688	
Miss Chat	2703 DF	No Shows
Kinderhook	2856 DF	
Hunton	3083 DF	
Sylvan	3285 DF	
Viola	3367 DF	No Shows
Simpson Dolomite	3485	
Simpson Shale	3511	
Simpson Sand	3566 DF	
Arbuckle	3580 DF	No Shows
3624 1/2 - 28 1/2	Had Por. but	
	no Sat.	