

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

5-11-14W

Pi

Compt. \_\_\_\_\_

SIDE ONE

Two (~~2~~) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5146 EXPIRATION DATE \_\_\_\_\_

OPERATOR Rains & Williamson Oil Co., Inc. API NO. 15-167-22,085

ADDRESS 435 Page Court, 220 W. Douglas COUNTY Russell

Wichita, Kansas 67202 FIELD \_\_\_\_\_

\*\* CONTACT PERSON Juanita Green PROD. FORMATION \_\_\_\_\_  
PHONE 265-9686

PURCHASER \_\_\_\_\_ LEASE Harrell

ADDRESS \_\_\_\_\_ WELL NO. #1

WELL LOCATION NE NE NW

DRILLING Rains & Williamson Oil Co., Inc. 330 Ft. from North Line and

CONTRACTOR \_\_\_\_\_ 2310 Ft. from West Line of

ADDRESS 435 Page Court, 220 W. Douglas the (Qtr.) SEC 5 TWP 11SRGE 14 (W)

Wichita, Kansas 67202

PLUGGING Same

CONTRACTOR \_\_\_\_\_

ADDRESS \_\_\_\_\_

WELL PLAT

(Office Use Only)


KCC  
KGS   
SWD/REP  
PLG.

TOTAL DEPTH 3475' PBTD \_\_\_\_\_

SPUD DATE 3-25-83 DATE COMPLETED 4-6-83

ELEV: GR 1782 DF \_\_\_\_\_ KB 1787

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE \_\_\_\_\_

Amount of surface pipe set and cemented 289' DV Tool Used? \_\_\_\_\_

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry Disposal, Injection, Temporarily Abandoned, OWWO. Other \_\_\_\_\_

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Wilson Rains, President, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Handwritten signature

OPERATOR Rains & Williamson Oil Co., LEASE Harrell #1 SEC. 5 TWP. 11S RGE. 14<sup>(W)</sup>

FILL IN WELL INFORMATION AS REQUIRED: WELL NO.

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Check if no Drill Stem Tests Run.				
DST #1 - 2720-2740, 30 (30) 30 (30). Rec. 120' mud. No pressures.			E. LOG TOPS	
DST #2 - 2720-2740, 30 (30) 30 (30). Rec. 15' OSM. FP's 51-51, 61-61. IBHP 469, FBHP 102.			Anhydrite	917 (+870)
			Topeka	2701 (-914)
			Heebner	2953 (-1166)
			Lansing	3006 (-1219)
			BKC	3276 (-1489)
DST #3 - 3008-3037, 30 (30) 30 (30). Rec. 5' mud. FP's 40-40, 40-40. IBHP 224, FBHP 91.			Congl.	3384 (-1597)
			Viola	3444 (-1657)
			LTD	3477 (-1690)
DST #4 - 3043-3053, 30 (30) 60 (30). Rec. 125' V.S1.OCMW. FP's 51-61, 81-91. IBHP 998, FBHP 888.				
DST #5 - 3077-3114, 30 (30) 30 (30). Rec. 2' mud. FP's 51-51, 51-51. IBHP 163, FBHP 122.				
DST #6 - 3170-3210, 30 (30) 30 (30). Rec. 10' mud. FP's 30-30, 40-40. IBHP 1007, FBHP 888.				
If additional space is needed use Page 2, Side 2				

Report of all strings set—surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (In O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	289'	Common	175 sx.	2% gel, 3% cc.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

  

TUBING RECORD		
Size	Setting depth	Packer set at