

9/13/83 pl

AFFIDAVIT OF COMPLETION FORM *
State Geological Survey
WICHITA BRANCH

ACO-1 WELL HISTORY KCC
Compt. 30-11-14W

TYPE -
SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5146 EXPIRATION DATE _____

OPERATOR Rains & Williamson Oil Co., Inc. API NO. 15-167-22,160

ADDRESS 435 Page Court, 220 W. Douglas COUNTY Russell
Wichita, Kansas 67202 FIELD _____

** CONTACT PERSON Juanita Green PROD. FORMATION _____
PHONE 265-9686

PURCHASER _____ LEASE Strecker #2

ADDRESS _____ WELL NO. _____

WELL LOCATION SE SE NE

DRILLING Rains & Williamson Oil Co., Inc. 2310 Ft. from North Line and

CONTRACTOR ADDRESS 435 Page Court, 220 W. Douglas 330 Ft. from East Line of (XX)

Wichita, Kansas 67202 the (Qtr.) SEC 30 TWP 11S RGE 14 (W)

PLUGGING Same WELL PLAT _____ (Office Use Only)

CONTRACTOR ADDRESS _____

TOTAL DEPTH 3540' PBTD _____

SPUD DATE 9-6-83 DATE COMPLETED 9-13-83

ELEV: GR 1806 DF _____ KB 1811

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE _____

Amount of surface pipe set and cemented 293' DV Tool Used? _____

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other _____

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Wilson Rains, President, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

WELL PLAT _____ (Office Use Only)

KCC _____
KGS
SWD/REP _____
PLG. _____

RELEASED
Date: OCT 1 1984
FROM CONFIDENTIAL

Wilson Rains

CONFIDENTIAL

OPERATOR Rains & Williamson Oil Co., Inc. Lease Strecker #2

SEC. 30 TWP. 11S RGE. 14

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO.

FORMATION DESCRIPTION, CONTENTS, ETC.		TOP	BOTTOM	NAME	DEPTH
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.				SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Check if no Drill Stem Tests Run.				E. LOG TOPS	
DST #1 - 2970-3038, 30 (30) 30 (30). Rec. 10' mud w/S1. show oil on top of tool. FP's 46-46, 46-57. IBHP 115, FBHP 92.				Anhydrite	912 (+899)
				B/Anhydrite	947 (+864)
				Topeka	2714 (-903)
				Heebner	2968 (-1157)
				Lansing	3023 (-1212)
				BKC	3289 (-1478)
				Congl. Shale	3367 (-155)
				Arbuckle	3507 (-1696)
				LTD	3540 (-1729)
Shale			115		
Shale, Shells, Clay & Sand			296		
Shale & Shells			905		
Shale			1633		
Shale & Shells			1933		
Shale & Lime			2780		
Lime & Shale			2915		
Lime			3076		
Lime & Shale			3145		
Lime			3540		
ROTARY TOTAL DEPTH			3540		

If additional space is needed use Page 2, Side 2

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	293'	Sunset	160 sx.	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

CONFIDENTIAL
DRILLER'S LOG

State Geological Survey
WICHITA BRANCH

COMPANY: Rains & Williamson Oil Co., Inc.

SEC. 30 T. 11S R. 14W

WELL NAME: Strecker #2

LOC. SE SE NE

COUNTY: Russell

RIG NO. #4

TOTAL DEPTH 3540'

ELEVATION 1806 GL 1811 KB

COMMENCED: 9-6-83

COMPLETED: 9-13-83

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 293' w/160 sx. Sunset

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Shale	115
Shale, Shells, Clay & Sand	296
Shale & Shells	905
Shale	1633
Shale & Shells	1933
Shale & Lime	2780
Lime & Shale	2915
Lime	3076
Lime & Shale	3145
Lime	3540
<u>ROTARY TOTAL DEPTH</u>	<u>3540</u>

RECORDED
INDEXED

OCT 6 1983

WICHITA BRANCH

STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

I, Wilson Rains, President

of Rains & Williamson Oil Co. Inc

Wilson Rains
10/13/83
Wichita