


DERBY OIL COMPANY - STEAMERS - STREETOR
 Dodge No. 2.

SEC. 32 T. 11 R. 15 W
 NEc SW SW

DEEPENING RECORD

Total Depth. 3181'
 Comm. 12-7-25 Comp. 2-5-26
 Shot or Treated.
 Contractor.
 Issued. 12-7-46

County. Russell



CASING.

15 1/2"	339' 3"	8 1/2"	2311' 10"
12 1/2"	838' 1"	65/8"	2835' 3"
10"	1424' 9"		

Elevation.

Production. 240 B.

Figures Indicate Bottom of Formation.

cellar	12	red rock	1878	shale green	2869
sand yellow and soft	27	broken lime grey	1894	Oil sand	
slate blue soft	115	slate blue	1902	Oswald Pay	2873 1/2
slate white soft	165	broken lime grey	1917	T.D.	
red rock red	210	red rock	1938		
sand grey	220	broken lime grey	1980	<u>DEEPENING RECORD</u>	
red rock red	300	red rock	2003	Old T.D.	2873 1/2
sand yellow	310	sand lime brown	2035	Comm. 10-6-29	
slate blue	335	slate brown	2045	Comp. 10-25-29	
sand yellow soft	345	lime grey	2060	Prod. 36 B. Oil per day	
slate blue	365	shale pink	2080	lime grey 2873 1/2	2888 1/2
red rock red	373	lime	2095	shale	2892
slate blue	388	slate blue	2105	lime	2898
sand grey	410	lime grey	2115	oil 2 1/2 BH	
slate blue	445	shale broken	2150	lime grey	2915
sand grey	475	slate blue	2200	lime grey hard	2921
slate pink	520	lime brown	2275	lime med	2925
red rock	650	Cave 2210		lime	2931
red rock	763	red rock	2278	lime hard	2935
iron	770	slate blue	2300	1 BW	
red rock	819	sand brown	2314	lime grey	2943
lime grey hard	840	lime brkn	2342	lime grey hard	2956
lime grey and hard	865	slate blue	2346	lime grey soft	2960
red rock	970	slate blue	2360	TD. P.B. 2903	
slate blue	1020	Cave 2350		<u>DEEPENING RECORD:</u>	
red rock	1040	lime	2380	Sohio Petro.Co.	
red rock	1093	slate blue	2405	Comm. 6-13-45	
slate brown	1125	lime	2415	Comp. 10-3-45	
slate blue	1159	2 BW 2410		Est. 45 B.	
salt brown	1250	shale dark	2480		
salt	1405	lime blk	2490		
slate blue	1415	slate blue	2500		
lime grey	1420	slate blue	2543		
slate blue	1437	1 BW 2543			
lime grey	1444	lime grey	2556		
slate blue	1460	slate blue	2566		
lime grey	1470	lime grey	2580		
slate blue	1490	slate blue	2593		
		fighting cave cement and		lime	2960-3172

lime grey	1505	fighting cave cement and	lime	2960-3172
slate grey	1530	water oil show 2600	Reagan Sand	3181
red rock real	1535	lime grey	Total Denth.	
red rock	1550	slate blue		
lime brown	1577	lime grey	2614	
slate blue	1589	shelly dark slate	2624	
red rock	1600	lime grey	2675	
slate blue	1635	shell slate blue	2685	
red rock	1665	broken lime	2715	
lime grey	1690	lime wh and hard	2750	
slate 1675		sdv lime brown	2795	
slate blue	1700	show oil and gas	2800	
broken lime	1740	lime white hard	2810	
slate blue	1750	slate sdv	2815	
lime	1785	lime ha rd	2820	
red rock	1805	lime grey hard	2822	
lime grey	1820	shale dark soft	2829	
slate blue	1832	shale	2835	
lime grey	1855	Dodge Pay	2840	
slate blue	1867	lime	2855	
lime grey	1870	shale blue	2858	
		shale brown	2862	

Ran 294' of 4 $\frac{1}{2}$ " liner
2815-3109 Cem.
Reagan Sand 3174 $\frac{1}{2}$
1st 2' sat. but tight
next 2 $\frac{1}{2}$ ' sat. & porous
Ran 79' 3 $\frac{1}{2}$ " liner from
3100-79. Started pmc
9-26-45. 1st 17 hrs
made 57 BO, no wtr
No electric logs run