

September, 1942

Snowden-Mc Sweeney, # 2 Booth  
NW SE SW, 32-11s-15w  
Elev. 1762'

Cable tools  
Lansing production only

Pennsylvanian Conglomerate 3167'-3175' (TD 3176')

3167-3169	Sand, very fine, silty, calcareous, in part friable, oilstained. Poor porosity.
3169-3172	Soft flaky gray shale.
3172-3175	Conglomerate of sand and chert, in part lime cemented. Part of sand grains are recrystallized medium, rarely coarse, and were derived from Pre Cotter sands. Cherts are white to purple, in part oolitic. Marine conglomerate.
3175-3176	No sample. Test made some oil and a large amount of water at 3176' TD and was plugged back to the Lansing.

---

---