

September, 1942

Stanolind, #B-1 Booth
(Midwest, # 4 Booth)
Samples labeled Stanolind, # 4 Booth
NE NW NE, 29-11s-15w

Cable tools OWDD

15-167-00517-0001

Elv 1905
Pennsylvanian Conglomerate 3230'-3253' TD

- 3230-3235 Clay shale, dark brick red with rare included sand grains. Samples include about 2% oxidized chert--probably imbedded in clay.
- 3235-3252 Clay, red, streaked and mottled gray. About 5% loose stained cherts, rounded.
- 3252-3253 Chert conglomerate. Varied oxidized cherts, worn, rounded. About 5% sand, largely rounded, medium and coarse. Cleaning-out sample, 3253' TD, includes some brown fine granular limestone interpreted as cavings. Marine conglomerate.

Remarks: Potential 364 bbls oil from pay 3252'-3253' TD.
