

118800, # D-1 lines
SW NE NW, 16-11s-15w
Elev. 1944'

Cable tools

15-167-06139

Two samples only. No others known to exist. Drilled 1941.

3403 Dolomite, brown, medium, cherty. 25% chert,
largely watery, flinty. Cotter.

3418-3422 Dolomite, dark brown, fine to medium, and some
white, dense, granular. 40% chert, quartzose
and abundantly oolitic. Basal Cotter.

Remarks: Top of Arbuckle from scout information is 3403' or -1459'
Driller's log shows lime from that point to 3453' TD where
HFW was encountered.

This test should have encountered the top of the Pre Cotter
at an estimated depth of 3330' or Subsea -1486' E

RFW