

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


9-11-15W ✓

Company- SOHIO PETROLEUM CO.
 Farm- Chrisler "B" No. 2

SEC. 9 T. 11 R. 15W
 NE NE SW

Total Depth. 3463'
 Comm. 3-30-63 Comp. 4-10-63
 Shot or Treated.
 Contractor. A. L. Jackson Drilling
 Issued. 10-26-63

County Russell
 KANSAS



CASING:
 10 3/4" 103' cem w/ 10#
 7" 3453' cem w/ 150 sx

Elevation. 1966' KB

Production. 7 BO plus 220 BWPD

Figures indicate Bottom of Formations.

shale	30
sand	55
shale & shells	370
sand	450
shale & sand	800
red bed	1044
anhydrite	1080
shale & shells	1640
lime	2290
lime & shale	2800
lime	3463
Total Depth	

TOPS: SMP	
Anhydrite	1044
Topeka	2791
Heebner	3043
Toronto	3065
Lansing	3092
Conglomerate	3423
Arbuckle	3450

DST #1, Op 1 hr. weak, steady blow 1 hr.
 Rec. 520' very slightly oil out mud.
 IBHP 435# 30 min. IFP 85#, FP 265#,
 FBHP 393#.

DST #2, Op 1 hr. weak blow dead in 5 min.
 Rec. 120' of drilling mud. IBHP 1009#
 in 30 min. IFP 13#, FP 296#, FBHP 940#
 in 30 min.