

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


9-11-15W

Company. COPPINGER DRILLING, INC., et al
Farm- Cook No. 1

SEC. 9 T. 11 R. 15W
NW SW NE

Total Depth. 3470
Comm. 11-25-55 Comp. 12-11-55
Shot or Treated.
Contractor. Coppinger Drilling, Inc.
Issued. 1-28-56

County Russell
KANSAS



CASING:
8 5/8 @ 148' w/ 100 sx cmt.
5 1/2 @ 3469' w/ 100 sx cmt.

Elevation. 1955 RB

Production. 25 BOPD

Figures Indicate Bottom of Formations.

native solids	40
sand	65
sand & shale	80
shale	148
shale & rock	370
sand	410
shale	500
shale & shells	845
shale, shells & red bed	1040
anhydrite	1070
shale	1650
shale & lime	2030
lime	2190
lime & shale	2370
shale	2635
shale & lime	2695
shale	2765
lime & shale	2895
lime	2995
lime & shale	3110
lime	3276
lime & shale	3400
lime	3470
Total Depth	

TOPS:	
Anhydrite	1040
Topeka	2778
Heebner	3026
Toronto	3047
Lansing	3088
Base K. C.	3334
Arbuckle	3407