

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


16-11-15W

Company- SOHIO PETROLEUM CO.
Farm- Hines "B" No. 5

SEC. 16 T. 11 R. 15W
SE SE NW

Total Depth. 3384
Comm. 1-23-57 Comp. 2-2-57
Shot or Treated.
Contractor. Bennett & Roberts Drlg Co.
Issued. 3-16-57

County Russell
KANSAS



Elevation. 1926 D.F.

CASING:

8 5/8" 1018 1/2' cem w/500 sx.
5 1/2" 3367' cem w/100 sx.

Production. 25 BOPD

Figures indicate Bottom of Formations.

surface soil, clay 30
sand 45
shale, sandy strks,
shells 250
shale blue & gray 390
red bed, shale 570
red bed, lime strks 655
pyrite 670
red bed, lime strks 795
red bed, shale blue
& shells 1007
anhydrite 1045
shale, shells, red bed 1100
shale, shells 1625
lime 1780
lime, shale 2878
lime 2937
shale, lime 3138
lime 3322
shale, chert 3367
arbuckle R.T.D. 3377
Cable Tools
lime 3384
Total Depth

Tops:

Anhydrite (Scout) 1007
Topeka 2742
Heebner 2992
Toronto 3012
Lansing-Kansas City 3040
Base Kansas City 3300
Arbuckle 3364

Pmped 31.74 BO / 13.26 BW / 24 hrs.
" 31.08 BO / 10.92 BW / 24 hrs.