

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


16-11-15W

Company- AYIWARD DRILLING CO. ET AL
Farm- Howe No. 3

SEC. 16 T. 11 R. 15W
C E/2 SW SE

Total Depth. 3410'
Comm. 3-16-64 Comp. 3-27-64
Shot or Treated.
Contractor. Aylward Drlg.
Issued. 6-20-64

County Russell
KANSAS



CASING:

Elevation. 1930' DF

8 5/8" 745' cem w/ 375 sx
5 1/2" 3405 1/2' cem w/ 150 sx

Production. 97 BOPD-NW

Figures Indicate Bottom of Formations.

surface clay & sand	40
sand & clay	130
shale & shells	255
shale	585
sand	1001
anhydrite	1037
shale	1625
shale & lime	1755
lime	2335
lime & shale	2750
lime	2845
lime & shale	3005
lime	3030
lime & shale	3105
lime	3210
lime & shale	3370
lime	3410
Total Depth	

TOPS: LOG

Topeka	2744
Heebner	2994
Toronto	3014
Lansing	3045
Arbuckle	3378

DST 2998-3030 Op 1 hr 10 min. Rec. 1260'
gas & 75' OCM IBHP 210# 30 min; FBHP 210#
30 min; FP 75#-80#

DST 3032-3105 Op 1 hr 10 min; Rec. 250'
mud, very sl show oil IBHP 395# 30 min ;
FBHP 370# 30 min; FP 110#-205#.

DST 3372-90' Op 1 hr 10 min. Rec. 40'
mud, few oil specks IBHP 305# 30 min;
FBHP 285# 30 min.; FP 35#-35#.