

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


16-11-15W

Company. AYLWARD DRILLING CO.
Farm- Whitson No. 2

SEC. 16 T. 11 R. 15W
SW SE SW

Total Depth. 3386
Comm. 6-25-55 Comp. 7-10-55
Shot or Treated.
Contractor. Aylward Drilling Co.
Issued. 9-3-55

County Russell
KANSAS



8 5/8 CASING: 103' w/ 75 sx cmt.
5 1/2 3385' w/ 150 sx cmt.

Elevation. 1901 RB

Production. 50 BOPD

Figures Indicate Bottom of Formations

surface clay	40
shale	103
shale & shells	240
Dakota sand	300
shale & red rock	850
shale & red bed	965
anhydrite	1005
shale & shells	1500
shale & broken lime	1715
shale & lime	1870
lime	2045
lime & shale	2185
lime	2255
shale & shells	2435
shale & lime	2865
lime	2925
shale & lime	3030
lime	3336
dolomite	3386
Total Depth	

TOPS:	
Topeka	2706
Heebner	2963
Toronto	2981
Lansing	3011
Arbuckle	3334

DST #1: 3204-15, open 30 min. fair
blow, rec. 300' gas, 15' OCM, 15'
wtry mud, IFP 30#, FFP 45#, BHP 2503/
15 min.

Diamod core 3333-82

Perf. 20 holes 3358-64
FU 290' oil overnight
Acid. w/ 250 gals: Tst 11 BQ/14 hrs.
set plug @ 3353, Perf. 23 holes
3345-53, 500 gals. acid. Tst 3 to 4
BOPH/ 3 hrs. set plug @ 3340, Perf.
15 holes 3334-40, 1000 gals acid.
Tst. 5 BOPH/5 hrs thru all perf.