

21-11-15W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- AYLDWARD DRILLING CO.  
Farm- Reich "B" No. 3

SEC. 21 T. 11 R. 15W  
SW NE NW

Total Depth. 3366'  
Comm. 3-9-56 Comp. 3-18-56  
Shot or Treated.  
Contractor. Aylward Drlg. Co.  
Issued. 5-12-56

County Russell  
KANSAS



Elevation. 1891' KB

Production. 25 BOPD

CASING:

8 5/8" 102' cem w/90 sx  
5 1/2" 3364' cem w/150 sx

Figures indicate Bottom of Formations

shale & clay	40
shale	300
sand & shale	450
red rock & shale	955
anhydrite	1010
red bed	1100
shale	1310
salt	1400
shale & shells	1890
lime	2028
shale & lime	2590
lime	2630
shale & shells	2780
shale, lime strks	2870
shale & lime	3020
lime	3040
lime & shale	3065
lime	3364 RTD
lime	3366
Total Depth	

Tops:

Heebner	2956
Toronto	2975
Lansing	3005
Base Kansas City	3238
Arbuckle	3330

Cable Tool Data:  
Drill cement to 3358, perf. 24 holes from 3340-47, test 2 BOPH natural, fill up 700' oil in 16 hrs.; acidize w/250 gals., swab 5 BOPH. Perf. 24 holes 3332-40 and 6 holes 3340-47, 1500 gals. acid, test 6 BOPH, POP