


21-11-15W ✓

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRILLING
Farm- Reich"C" No. 1

SEC. 21 T. 11 R. 15W
SE SE SE

Total Depth. 3370'
Comm. 7-21-65 Comp. 7-28-65
Shot or Treated.
Contractor. Aylward Drlg.
Issued. 10-23-65

County Russell
KANSAS


CASING:

5½" 3369' cem w/ 150 sx

Elevation. 1863' KB

Production. TEMP ABDN

Figures Indicate Bottom of Formations.

surface clay	122
shale	550
sand	620
shale	925
anhydrite	950
shale w/ lime strks	1070
blue shale	1200
shale & lime	1685
shale	1860
lime	2005
lime & shale	2640
shale	2738
lime	2952
shale & lime	3009
lime	3370 RTD
Total Depth	

TOPS:	LOG	SMP
Topeka	2700	2696
Heebner	2955	2952
Toronto	2974	2972
Lansing	3007	3004
Base Kansas City	3240	3236
Arbuckle	3325	3319

DST 3098-3110- Op 1 hr. Rec. 160' muddy S.W.
IBHP 298# 30 min; FBHP 111# 30 min; FP
29-59#;

DST 3323-38 Op 1 hr. Rec. 65' SL. OCM
IBHP 907# 30 min; FBHP 854 # 30 min;
FP 44 - 59#.

DST 3316-48 Op 1 hr. Rec. 10' Heavy OCM,
60' SL. OCM. IBHP 980# 30 min; FBHP 842#
30 min; FP 60-110#.