

21-11-15W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **AYLWARD DRILLING**
Farm- **REICH "D"** No. **1**

SEC. 21 T. 11 R. 15W
NW NE SW

Total Depth. **3355'**
Comm. **7-29-65** Comp. **8-7-65**
Shot or Treated.
Contractor. **Aylward Drilling**
Issued. **10-23-65**

County **RUSSELL**
KANSAS



CASING:

5 1/2" 3346' cem w/ 150 sx

Elevation. **1888'** KB

Production. **25 BO PLUS TR W**

Figures Indicate Bottom of Formations.

soil & clay	100
post rock	155
shale	235
gumbo w/shale strks	380
shale	960
anhydrite	991
shale	1280
broken shale & lime	1555
lime w/shale strks	1700
shale	1840
lime w/ shale	1860
lime & shale	2400
shale	2712
lime	3240
lime w/shale brks	3248
lime	3355
Total Depth	

DST 3331-55 Op 1 hr. Rec. 30' **HOLCOM**,
180' **M&CO** BHP 1006# 30 min; 945# 30 min;
FP 29-96#.

TOPS: LOG	
Topeka	2711
Plattsmouth	2889
Heebner	2966
Toronto	2986
Douglas	3000
Lansing	3020
Arbuckle	3344

DST 2897-2983 Op 1 hr. Rec. 420' muddy
S.W. BHP 892# 30 min; 862# 30 min; FP
104-335#.

BST 2988-3050 Op 1 hr. Rec. 125' mud w/
spots oil BHP 380# 30 min; 327# 30 min
FP 89-111#.

DST 3175-3240 Op 40 min. Rec. 15' mud.
BHP 357# 30 min; 327# 30 min; FP 67-74#