

20-11-15W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SUMMIT OIL COMPANY
Farm- Bronson "B" No. 1

SEC. 20 T. 11 R. 15W
 NW SW SE

Total Depth. 3300
Comm. 8-11-51 Comp. 8-22-51
Shot or Treated.
Contractor. Stearns petroleum, Inc.
Issued. 11-10-51

County Russell
 KANSAS



CASING:
8 5/8" 142' cem w/ 75' sx.
5 1/2" 3300' cem w/ 125' sx.

Elevation. 1795 D.F.
 1797 (and)
Production. Pmped 30 bbls

Figures Indicate Bottom of Formations.

surface clay	40
shale blue	142
shale, sand	525
red bed, shale, iron	850 ✓
shale, red bed	875
anhydrite	908
shale, shells	1040
shale	1250
salt, shale	1445
shale, shells	1735
lime, shale	2610
lime Topeka	2858
shale heebner	2912
lime lansing	3226
conglomerate	3273
arbuckle lime	3300
Total depth	

Tops:	
Anhydrite	875
Topeka Lime	2610
Heebner Shale	2858
Lansing Lime	2912
Conglomerate	3226
Arbuckle Lime	3273