


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRILLING COMPANY
Farm- Booth No. 6

SEC. 32 T. 11 R. 15W
SE SE SW

Total Depth. 3162
Comm. 12-11-56 Comp. 12-21-56
Shot or Treated.
Contractor. Aylward Drlg Co.
Issued. 3-16-57

County Russell
KANSAS



CASING:

8 5/8" 215' cem w/150 sx.
5 1/2" 3152'

Elevation. 1742 KB

Production. 25 bbls oil per day

Figures indicate Bottom of Formations.

sand, shale, shells	110
shale, shells	215
shale, sand	510
shale, shells, redbed	790
anhydrite	815
shale, shells	1390
shale, lime	1430
shale, shells	1550
lime	1660
lime broken	1745
shale, shells	1810
lime, shale	2170
shale, brk.	2185
shale, lime	2245
shale	2390
shale, shells	2665
shale, lime	2825
lime	3140
Diamond Core RTD	3156
lime	3162
Total Depth	

Tops:

Anhydrite	790
Topeka	2566
Heebner	2788
Toronto	2809
Lansing	2840
Base Kansas City	3072
Reagan	3151

DST 2740-65 Open 1 hr.; good
blow throughout. Rec. 1620' wtr
BHP 1175/20 min.; FP 60#-725#.

DST 2794-2825 Open 1 hr.; good
blow throughout. Rec. 200'
free gas in drill pipe plus
100' O & GCM; BHP 40#/20 min.

DST 2821-75. Open 1 hr. Fair
blow throughout. Rec. 27' SI
OCM, 90' very slightly OC watery
mud. BHP 175#/20 min.