

**KANSAS GEOLOGICAL SOCIETY**  
**KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU**  
**KANSAS GEOLOGICAL SOCIETY BUILDING**  
**508 EAST MURDOCK - WICHITA, KANSAS**

COMPANY JOHN O. FARMER

SEC. 33 T. 11 R. 15W  
 LOC. SW SW NW

FARM Abbott

NO. 1

TOTAL DEPTH 3295'

COMM. 5-26-66

COMP. 6-3-66

SHOT OR TREATED

CONTRACTOR Shields Drlg.

ISSUED 8-6-66

COUNTY Russell



CASING

20	10	
15	8 5/8" 167'	cem w/ 130 sx
12	6	
13	5	

ELEVATION 1766' KB

PRODUCTION DRY

FIGURES INDICATE BOTTOM OF FORMATION

Post rock and shale	167'
Shale, shells and pyrite	590'
Shale and shells	845'
Anhydrite	880'
Shale and shells	1,000'
Salt, shale and shells	1,450'
Shale and lime	1,700'
Lime	1,930'
Lime and shale	2,700'
Lime	3,265'
Lime and chert	3,295' RTD

TOPS: SCOUT

Anhydrite	845
Dover	2370
1st Tarkio sand	2390
Tarkio lime	2411
2nd sand	2443
Topeka	2623
Heebner	2874
Toronto	2895
Lansing	2926
Base Kansas City	3182
Conglomerate sand	3244
Conglomerate chert	3264