

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - ANSCHUTZ DRLG.,
Farm - Eulert "B"

No. 1

SEC. 35
NW SW NE

T. 11


R. 15W

Total Depth. 3311
Comm. 11-4-49
Shot or Treated.
Contractor.
Issued. 1-7-50

Comp. 11-15-49

County. Russell

KANSAS



Elevation. 1836 feet.

Production. Phys. 99 bbls.

CASING:

8 5/8" 118' surface cen. w/100 sx.
5 1/2" 3304' cen. w/75 sx.

Figures Indicate Bottom of Formations.

surface rock	133
shale & shells	320
surface shale	375
Dakota sand	450
shale	490
pyrite	515 ✓
shale & shells	620
sand, shale	880
anhyd.	915
red bed	1030
shale & shells	1225
salt	1310
shale & shells	1660
lime & shale	2290
shale & shells	2678
lime & shale	2810
lime	2853
lime & shale	2995
lime	3307
lime	3311

Tops:

Heebner	2941
Toronto	2962
Lans. K.C.	2992
Arbuckle	3303