


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - ATLANTIC REFG. CO.
Farm - Mulert "B" No. 2

SEC. 35 T. 11 R. 15W
NW NE SW

Total Depth. 3234
Comm. 2-22-50 Comp. 3-13-50
Shot or Treated. acid.
Contractor. Anschutz Drlg.
Issued. 5-13-50

County. Russell
KANSAS



CASING:

8 5/8" 246' cem. w/200 sx. (RKB)
5 1/2" 3216' cem. w/200 sx.

1969(m)
Elevation. 1771 RB *Sub*

Production. 23 bbls. state test
25 BBL/D

Figures Indicate Bottom of Formations.

shells & shale	252
shale & shells	400
pyrite & sand	455 ✓
shale	500
red bed	830
an yd.	870
shale & shells	1235
salt	1340
shale & shells	1650
lime & shale	3030
lime	3145
lime & shale	3220
limo	3226
dolo.	3232
dolo.	3234
Total Depth	

Tops:
Casing 2917
Arbuckle 3214

Producing area: 3216-3232

Jetted 7 1/2% acid 3 hrs, 20 mins.
Lost 750 gals. acid. Spotted 500 gals.
15% acid. Pressure roke 650# to 300#.
Swabbed 2 3/4 BOPH.
Treated w/2500 gals. 15% acid down tubing.
900# press. on casing & 700# pr ess. on
tubing. Press. dropped to 200 # after
displacing 1150 gals. & to 0 on completion
of job. Swabbed 3 1/2 BOPH.
Perforated 3218-3222 w/1/4 jet holes per ft.
No increase.