

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL

FARM Krueger Ut

NO. 802

SEC. 1 T. 11 R. 16W
LOC. SE SE NW
2240 FNL & 2310FWL

TOTAL DEPTH 3405'

COMM. 4-11-66

COMP. 4-19-66


SHOT OR TREATED

CONTRACTOR Peel Bros.

ISSUED 8-13-66

COUNTY Ellis

KANSAS



CASING

20	10	
15	8 5/8" 247'	cem w/ 200 sx
12	6	
13	5 1/2" 3404'	cem w/ 150 sx

ELEVATION 1924' KB

PRODUCTION 146 BO PLUS 89 BWPD
(Lans 3136-40)

FIGURES INDICATE BOTTOM OF FORMATIONS

Casing Record:

8 5/8" at 247' W/200 Sacks
5 1/2" at 3404 - D.V. Tool at 1122'
Lower stage 150 Sx. - upper stage 300 Sx.

Formation Record:

	<u>Depth</u>
Clay and Sand	0- 30
Shale	335
Shale and Sand	1107
Anhydrite	1142
Shale and Shells	1660
Shale and Lime	2000
Lime W/shale streaks	2110
Lime and Shale	2819
Lime	3060
Shale (Heeb)	3063
Lime & Shale	3155
Lime	3405

Electric Log Tops:

SCOUT

Topeka	2819' (-895)	2821
Heebner	3058' (-1134)	3060
Toronto	3080' (-1156)	3081
Lansing	3109' (-1185)	3109
Base Kansas C.	3355' (-1431)	
LTD	3375'	

Slope Tests: Eastman

1643	1 1/2°
2625	1°