

SIDE TWO

Operator Name OXY USA Inc. Lease Name Gish C Well # 4
 Sec 2 Twp 11S Rge 16 X East County Ellis

RECOMPLETED FORMATION DESCRIPTION:

X Log Sample

<u>Name</u>	<u>Top</u>	<u>Bottom</u>
Topeka	2936'	2942'

Ran Welex GRN/CBL/CCL from 3150-2600'. Set CIBP at 3150'; dumped 1 sx cmt. w/Baler on CIBP.

ADDITIONAL CEMENTING/SQUEEZE RECORD

Purpose:	Depth		Type of Cement	# Sacks Used	Type & Percent Additives
	Top	Bottom			
Perforate	<u>Pumped 150 sx</u>	<u>60/40 Poz +2% gel +</u>	<u>2% cc, followed by 50 sx common</u>		
Protect Casing	<u>+2% cc.</u>				
X Plug Back TD					
Plug Off Zone					

Shots Per Foot	PERFORATION RECORD		Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)
	Specify Footage of Each Interval Perforated		
4	3109-12' (Set 5-1/2" CIBP at 3100')	350 gal/ft. 15% NE acid ; Spotted 1 sx cmt. on CIBP)	
4	2936-2942'	650 gals. 15% NE acid. 1500 gals. gelled 2% KCL water, followed by 2000 gal 28% SGA acid.	

PSTD 3100' Plug Type CIBP

TUBING RECORD:

Size 2-3/8" Set At 2936' Packer At --- Was Liner Run? Y X N

Date of Resumed Production, Disposal or Injection 4-26-1989.

Estimated Production Per 24 Hours 13 bbl/oil 8 bbl/water

-- MCF gas -- gas-oil ratio