

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


Company- SHIELDS OIL PRODUCERS  
Farm- Craig No. 1

SEC. 16 T. 11 R. 16W  
NE NE SW

Total Depth. 3354'  
Comm. 11-8-57 Comp. 11-24-57  
Shot or Treated.  
Contractor. Shields Drilling Company, Inc.  
Issued. 3-22-58

County Ellis

KANSAS



Elevation. 1784' RB

Production. 26 BBH

CASING:

8 5/8" 260' cem w/150 sx  
5 1/2" 3347 1/2' cem w/150 sx

Figures Indicate Bottom of Formations.

surface clay, lime shale	120
shale, sand	134
sand	150
shale, shells & sand	370
shale & sand	500
sand, iron, shale	655
red bed	676
red bed & shale	937
Anhydrite	973
shale & shells	1195
shale & shells; salt; shale & lime streaks	1635
shale & shells; lime streaks	1780
lime & shale	1890
lime; shale streaks	1980
lime & shale	2710
lime	2773
shale & lime	2814
lime	3058
lime, traces of chert	3105
lime	3173
lime & shale	3235
lime, Conglomerate	3307
lime	3354-RTD
Total Depth	

TOPS:

Heebner	2932
Lansing - Kansas City	2982
Chert Conglomerate	3270
Simpson Shale	3314
Arbuckle	3346

D.S.T. #1, 3010-40, Tool open 1 hr. w/steady blow thruout;  
Rec. 420' gal, 120' OCM, 60' muddy oil;  
BHP - 950#/20 min.

D.S.T. #2, 3347-54, Tool open 1 hr. w/good blow thruout;  
Rec. 60' oily mud, 865' oil; BHP -  
1090#/20 min.