


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SHIELDS OIL PRODUCERS
Farm- Craig No. 2

SEC. 16 T. 11 R. 16W
SW NE SW

Total Depth. 3359'
Comm. 4-23-58 Comp. 5-6-58
Shot or Treated.
Contractor. Shields Drilg. Co.
Issued. 6-28-58

County Ellis
KANSAS



CASING:
8 5/8" 272' cem w/200 sx.

Elevation. 1790' RB

Production. Dry

Figures Indicate Bottom of Formations.

sand & shale	60
shale & shells	195
shale, sand, iron	645
shale & shells	946
anhydrite	983
shale, shells, red bed	1050
shale & shells	1450
shale & broken lime	1645
broken lime	1775
lime, shale, chert	1875
broken lime	2085
shale & shells	2745
lime	2790
lime & shale	2840
lime	2890
lime & shale	2943
Heebner	2947
lime	2950
shale & lime	3055
lime	3155
shale & lime	3200
lime	3265
lime, shale, conglomerate	3320
lime, shale, chert	3345
Conglomerate & lime	3359 RTD
Total Depth	

TOPS:

Heebner	2944
Toronto	2966
Lansing-Kansas City	2993
Ch. Conglomerate	3282
Simpson Shale	3311
Arbuckle	3355

DST #1 3356-3359', op 2 hrs w/weak
blow, rec. 60' gas, 60' muddy oil, 60'
oily water, 30' water w/trace of oil.
BHP 1053#/20 min.