

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- SHIELDS OIL PRODUCERS  
Farm- Craig No. 3

SEC. 16 T. 11 R. 16W  
SE NE SW

Total Depth. 3349'  
Comm. 8-11-60 Comp. 8-20-60  
Shot or Treated.  
Contractor. Shields Drlg. Co.  
Issued. 11-12-60

County Ellis

KANSAS



Elevation. 1790' RB

Production. 104 BOPD

CASING:

8 5/8" 953' cem w/400 sx.  
4 1/2" 3348' cem w/150 sx.

Figures indicate Bottom of Formations.

surface soil, sand, post rock	75
sand, shells & shale	830
shale, shells, red bed	942
Anhydrite	980
shale, shells & salt	1500
shale w/lime	1915
lime & shale	1955
lime	1985
lime w/shale	2965
lime	3349 RTD
Total Depth	

TOPS:

Heebner	2934
Toronto	2956
Lansing-Kansas City	2982
Cherty Conglomerate	3272
Simpson Shale	3316
Arbuckle	3346

DRILL STEM TESTS:

#1 3011-3045', op 1 hr w/weak blow, rec.  
300' gas, 80' HOCM, 40' water. IFP 35#,  
FFP 70#, BHP 440#/20 min.

#2 3058-3092', op 1 hr w/good blow, rec.  
600' gas, 210' O & GC mud, 210' muddy oil.  
IFP 55#, FFP 190#, BHP 530#/20 min.

#3 3137-3171', op 1 hr w/good blow. rec.  
540' gas, 120' muddy oil, 180' clean oil,  
IFP 55#, FFP 120#, BHP 250#/20 min.