


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **HOUSTON PETROLEUM & CHIEF DRG. CO.**
 Farm- **Lundy No. 1**

SEC. **16** T. **11** R. **16W**
 CWL NW SE

Total Depth. **3355'**
 Comm. **8-7-59** Comp. **8-18-59**
 Shot or Treated.
 Contractor. **Chief Drlg.**
 Issued. **12-10-60**

County **Ellis**
KANSAS



CASING:
 8 5/8" 220' cem w/150 sx.
 5 1/2" 3353' cem w/150 sx.

Elevation. **1790' RB**

Production. **149 BOPD**

Figures indicate Bottom of Formations.

shale	245
sand	300
shale, sand & clay	520
shale & sand	540
sand	585
shale, shells & sand	650
shale, red bed & sand	
shells	945
Anhydrite	980
shale & shells	1630
lime with shale	1675
lime & shale	1815
lime	2105
lime & shale	2595
shale & lime	2700
lime	3250
cherty limestone	3315
shale & sand	3352
dolomite	3355
Total Depth	

TOPS:

Anhydrite	945
Heebner	2930
Toronto	2953
Lansing	2980
Base Kansas City	3222
Cherty-Conglomerate	3278
Simpson	3319
Arbuckle	3352