


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
 508 East Murdock, Wichita, Kansas

Company- HOUSTON PETROLEUM CO.  
 FarmLundy No. 3

SEC. 16 T. 11 R. 16W  
 C W/2 W/2 SE

Total Depth. 3355'  
 Comm. 10-19-59 Comp. 10-30-59  
 Shot or Treated.  
 Contractor. Chief Drlg. Co.  
 Issued. 2-13-60

County Ellis KANSAS



**CASING:**

8 5/8" 952' cem./275 sx.  
 5 1/2" 3354' cem./35 sx.

Elevation. 1786 DF.

Production. 98 BOPD

Figures Indicate Bottom of Formations.

shale & shells	275
sand & shale	480
shale & shells	550
sand & shale	600
shale & shells	740
shale, redbed & shells	880
shale, redbed & anhy.	948
Anhy.	980
Red Bed, shale & shells	1100
shale & shells	1575
shale & lime	1690
shale, lime & sand	1885
lime & shale	2450
shale, lime & shells	2585
shale & shells	2730
shale & lime	2850
lime	2931
lime & shale	2994
lime	3226
lime, shale & sand	3353
dolomite	3355
Total Depth	

**TOPS:**

Anhydrite	942
Topeka	2692
Heebner	2931
Toronto	2952
Lansing-Kansas City	2981
Base Kansas City	3224
Conglomerate	3276
Simpson	3318
Arbuckle	3353