


*Plotted
Albert Wheeler*

LARIO OIL & GAS CO.
Romine No. 1.

SEC. 18 T. 11 R. 16W
NW SW NW

Total Depth. 3317'
Comm. 6-29-37 Comp. 8-13-37
Shot or Treated.
Contractor. Broadwater Drlg.Co.
Issued. 8-21-37

County. Ellis



Elevation.

CASING:
10" 850'
7" 3312'

AUG 21 1937

Production. Pot. 1685 R.

Figures Indicate Bottom of Formations.

surface hole	50	lime	2649
shale	70	shale & shells	2700
shale & shells	140	lime	2720
sand	152	lime & shale	2756
lime	172	lime	2940
shale & shells	224	shale	2947
shale	385	lime	3004
sand & shale	398	shale	3009
shale & shells	438	lime	3109
sand	525	shale	3128
lime & pyrites	540	lime	3297
lime	555	cored 3302-3315	
sand & pyrites	740	shale green	3312
shale	810	lime	3317
shale & shells	867	Total Depth.	
red rock & shale	967		
red rock	979	Top Siliceous	3312
anhydrite & lime	1017		
red rock & shells	1043		
shale & shells	1270		
shale & lime	1350		
sand, lime & shale	1428		
salt	1448		
shale	1525		
lime & shells	1568		
shale & shells	1660		
shale	1685		
lime	1710		
brkn lime & shells	1734		
lime	1757		
brkn lime & shale	1816		
brkn lime	1876		
lime	1894		
shale & lime	1934		
lime	2082		
shale & shells	2134		
shale	2154		
lime	2235		
shale	2255		
lime	2309		
shale	2319		
lime	2350		
shale	2399		
lime	2425		
shale, lime & shells	2480		
brkn lime	2530		
lime	2554		
shale	2580		
shale & shells	2631		